

SAFETY FACTOR ASSESSMENT PERIODIC 5-YEAR REVIEW

CFR 257.73e

East Bottom Ash Pond

Rockport Plant
Rockport, Indiana

October 2021

Prepared for: Indiana Michigan Power Company

Prepared by: American Electric Power Service Corporation

1 Riverside Plaza
Columbus, OH 43215




AEP Unique Document ID: GERS-21-036

SAFETY FACTOR ASSESSMENT
PERIODIC 5-YEAR REVIEW
CFR 257.73(e)
ROCKPORT PLANT
EAST BOTTOM ASH POND

PREPARED BY *Dan Murphy* DATE 9/29/2021
Dan Murphy, P.E.

REVIEWED BY *M.A.L.* DATE 9/29/2021
Mohammad Ajlouni, Ph. D, P.E.

APPROVED BY *Gary F. Zych* DATE 9/29/2021
Gary F. Zych, P.E.
Section Manager – AEP Geotechnical Engineering



I certify to the best of my knowledge, information, and belief that the information contained in this safety factor assessment meets the requirements of 40 CFR § 257.73(e)

Table of Contents

1.0	Introduction	4
2.0	Description of the CCR Unit	4
3.0	Subsurface Conditions	5
3.1	Site Geology	5
3.2	Review of Historical Soil Borings	5
4.0	Geotechnical Analysis	6
4.1	Strength Parameters	6
4.2	Phreatic Surface & Pond Levels	6
4.3	Load Cases Analyzed	7
4.4	Liquefaction Considerations	8
5.0	Results	9
6.0	Conclusions	10

List of Appendices

- Appendix A: Site Map
- Appendix B: Slope/W Outputs
- Appendix C: Historical Soil Borings & Geotechnical Data
- Appendix D: Original Design Drawings

List of Tables:

- Table 1: Engineering Properties used in Safety Factor Assessment
- Table 2: Load Cases Analyzed for the North-to-South Splitter Dike
- Table 3: Load Cases Analyzed for the East to West Splitter Dike
- Table 4: Safety Factor Assessment Summary for the North to South Splitter Dike
- Table 5: Load Cases Analyzed for the East to West Splitter Dike

1.0 Introduction

This report was prepared by AEP- Geotechnical Engineering Services (GES) section to fulfill requirements of 40 CFR §257.73(e) for the safety factor assessment of CCR surface impoundments. This report was prepared to meet the requirements for the first 5-year periodic review of the safety factor assessment.

Since the original 2016 Safety Factor Assessment, the CCR electronic operating records for the East and West Bottom Ash Ponds have split. The former operating record was for the Bottom Ash Pond Complex and was considered inclusive for both the East and West Bottom Ash Ponds. Since the splitter dike between the East and West Bottom Ash Pond is now considered to separate two separate CCR Units, this report will analyze the safety factor for the splitter dikes separating the two bottom ash ponds. In addition, this report will further analyze the splitter dike between the bottom ash ponds and the wastewater ponds.

2.0 Description of the CCR Unit

The Rockport plant is located near the City of Rockport, Spencer County, Indiana. It is owned by Indiana Michigan Power Co. (I&M), a unit of American Electric Power. The facility operates two surface impoundments for storing CCR within the Bottom Ash Complex. The bottom ash ponds and wastewater ponds were designed in tandem; one bottom ash pond and one wastewater pond are in service at any given time.

There are six main ponds within the bottom ash pond complex as listed below.

List of Main Ponds within the Bottom Ash Complex

- West Bottom Ash Pond
- East Bottom Ash Pond
- West Waste Water Pond
- East Waste Water Pond
- Reclaim Pond
- Clear Water Pond

The East Bottom Ash Pond is incised on the northern and eastern sides of the pond. A north-to-south trending splitter dikes separate the East Bottom Ash Pond from the West Bottom Ash Pond. An east-to-west trending splitter dike separates the East Bottom Ash Pond from the East Wastewater Pond.

The north-to-south trending splitter dike is approximately 2,000 feet long and has a maximum design height of 22 feet. The top of the dike is at elevation 399. The design height is measured from the crest of the dike to the floor of the East Bottom Ash Pond. The dike is constructed out of compacted cohesive soil. Both interior and exterior slopes are designed to be 2 Horizontal to 1 Vertical. Native soil is estimated around elevation 390, based on original design drawings.

The east-to-west trending splitter dike is approximately 650 feet long and has a maximum design height of 24 feet. The top of the dike is at elevation 399. The design height is measured from the crest of the dike to the floor of the East Waste Water Pond. The dike is constructed out of compacted soil. Both

interior and exterior slopes are designed to be 2 Horizontal to 1 Vertical. Native soil is estimated around elevation 390, based on original design drawings.

3.0 Subsurface Conditions

3.1 Site Geology

The site of Rockport Bottom Ash Ponds is within the flood plain of the Ohio River and the Boonville Hills physiographic province of the Southern Hills and Lowlands physiographic region.

According to the USDA Soil Survey of Spencer County, Indiana (September 2015), the predominant soil in the vicinity of the site is the Ginat silt loam (Gn). The Weinbach silt loam (WcA), Sciotoville silt loam (ScA and ScB2), and Wheeling loam (WhB2) are also present near the facility, but to a lesser extent. A majority of the soils in the vicinity of the site have been altered or removed during site development and are classified as Udorthents (Uaa) or Mine Dumps (Du).

The Ginat consists of poorly-drained silt loam and silty clay loam. The Weinbach consists of somewhat poorly drained silt loam and silty clay loam. The Sciotoville and Wheeling consist of moderately well-drained to well-drained silt loam, clay loam, and loam.

The Bottom Ash Ponds are located on the western bank of the Ohio River and is underlain by Quaternary age alluvium consisting of Wisconsinan age undifferentiated outwash. Geotechnical borings performed at the site during the original subsurface investigation indicate clay generally ranging from less than 5 to about 15 feet in thickness, but may extend up to about 30 feet and contain layers or lenses of fine sand. The clay layer was underlain by fine to coarse sand deposits. Historical boring information is presented in Appendix C.

Bedrock consists of the Raccoon Creek Group Formation of Pennsylvanian age and is comprised of predominantly shale and sandstone with thin beds of limestone, clay, and coal. The Raccoon Creek Group is underlain by rocks ranging in age from Middle Devonian to Late Mississippian and is located at about elevation 280 to 300 feet.

Structurally, the area is located within the Illinois Basin, near the eastern border of the Wabash Valley Seismic Zone, which generally consists of vertically-oriented faults buried under layers of sediment.

3.2 Review of Historical Soil Borings

A review of historical borings information was performed to develop a soil profile and define soil shear strength properties. Relevant historical geotechnical borings and laboratory testing data is included in Appendix C of this report. In 2016, Terracon performed two soil borings through the western dike of the West Bottom Ash Pond.

In addition, soil boring logs for monitoring wells 1604, 1605, and 1606 were also used to develop a soil profile. The top of natural soil horizon is based on the original construction-grading plan for the Bottom Ash Ponds.

4.0 Geotechnical Analysis

Slope stability analysis was performed using Slope /W 2012 Version 8.14.2 developed by Geo-Slope International, Ltd. The Morgenstern-Price Method was to solve 2-Dimension Limit Equilibrium equations.

The critical slip surfaces were found by specifying the entry and exit locations of the potential slip surfaces. For all cases analyzed, the potential entry point for the slip surface was taken from the centerline of the crest and extended about 1/3 over the slope transition. The range of exit locations for the slip surfaces starts about 1/3 the way up the slope and extends about 20 feet beyond the toe of the slope. For both the entry & exit locations, 10 increments were used to search for the critical slip surface.

Seismic loading was performed using a horizontal seismic coefficient of 0.145. The seismic coefficient considers ½ of the 2008 Peak Ground Acceleration with 2% Probability of Exceedance in 50 Years for firm rock (0.22), with an amplification factor of 1.32. This seismic coefficient is consistent with seismic loading parameters from Terracon’s 2016 Safety Factor Assessment report.

Rapid drawdown scenarios were modeled due to adjacent pond operations for the splitter dikes. The Duncan, Wright, and Wong (1990) method was used to define the shear strength properties of soils subjected to drawdowns. Total stress shear strength properties are applied to soils that would be subjected to drawdowns.

4.1 Strength Parameters

Strength parameters were developed based on the results of the field and laboratory testing. Soil profiles were developed based on subsurface conditions interpreted from the borings. Table 1 summarizes the engineering properties used in the Safety Factor Assessment. Shear strength parameters assigned to the soil profile were based on the Standard Penetration Test n-Values and the consolidated-undrained Triaxial compression tests performed by Terracon in 2016 in nearby boring locations.

Material	Unit Weight (pcf)	Effective Stress Parameters		Total Stress Parameters	
		Φ' (degree)	C' (psf)	Φ (degree)	C (psf)
Embankment Fill	130	29	50	19	400
Foundation Clay	123	34	50	22	200
Loose Sand	115	30	0		
Medium Dense Sand	123	33	0		
Riprap	150	42	0		

4.2 Phreatic Surface & Pond Levels

The phreatic surface modeled in the Safety Factor Assessment assumes a simple straight line through the dike cross section. The maximum operating pools as modeled were based on original design

drawing (AEP Drawing 12-30027-8). The author believes this is a slightly conservative assumption, but is relevant given the absence of piezometers within the embankment dams.

4.3 Load Cases Analyzed

4.3.1 North to South Splitter Dike

Scenarios where maximum hydrostatic pressures differences across the splitter dike were selected as critical. If both adjacent ponds are in service and impounding the maximum operating pools, the hydrostatic pressure difference across the splitter dike is essentially equal and therefore was not analyzed. A scenario where the splitter dike experiences hydrostatic loading from one ash pond while the other pond is drained for cleanout has occurred in past operations and both scenarios were included in the load cases analyzed.

The eastern facing slope of the north to south splitter dike is greater than the western facing slope due to the deeper pond bottom for the East Bottom Ash Pond.

Scenario Description	West Bottom Ash Pond Phreatic Surface Elevation	East Bottom Ash Pond Phreatic Surface Elevation	Commentary
WBAP In Service; EBAP Drained	396	376	Routine operations
WBAP Drained; EBAP In Service	385	396	Routine operations
Seismic- WBAP In Service, EBAP Drained	396	376	Splitter dike height greater on eastern slope.
WBAP in Flood Stage; EBAP Drained	396.6	376	100-year flood. Splitter dike height greater on eastern slope.
Rapid Drawdown of East Bottom Ash Pond	396	396 to 376	Per Duncan, Wright & Wong (1990)
Rapid Drawdown of West Bottom Ash Pond	396 to 385	396	Per Duncan, Wright & Wong (1990)

4.3.2 East to West Splitter Dike

The east to west splitter dike separates the East Bottom Ash Pond from the East Wastewater Pond. The East Pond Ash Pond is typically dewatered during routine bottom ash removal operations. The East Wastewater Pond is typically impounding normal pool while the East Bottom Ash Pond is emptied for cleanout. Therefore, a scenario where the East Bottom Ash Pond is in service and the East Wastewater pond is emptied was not analyzed.

Scenarios where hydrostatic pressure differences across the splitter dike were selected as critical. If both adjacent ponds are in service and impounding the maximum operating pools, the hydrostatic pressure difference across the splitter dike is roughly ½ of that experienced when the East Bottom Ash Pond is empty. Therefore, a scenario where both the East Wastewater Pond and the East Bottom Ash Pond are in service at maximum operating pool is not the critical load case and was not analyzed.

Scenario Description	East Wastewater Pond Water Surface Elevation	East Bottom Ash Pond Water Surface Elevation	Commentary
EBAP Drained, EWWP In Service	389	376	Routine operations
Seismic- EBAP Drained, EWWP In Service	389	376	
EBAP Drained, EWWP at Flood Stage	389.6	376	100-year flood surcharge pool.
Rapid Drawdown of East Bottom Ash Pond	389	396 to 376	Duncan, Wright & Wong (1990)

4.4 Liquefaction Considerations

In addition, the CCR rules require that for dikes constructed of soils with a susceptibility to liquefaction, the calculated factor of safety against liquefaction must equal or exceed a value of 1.20. The splitter dikes are constructed predominantly of lean clay containing varying amounts of sand and is not considered to be susceptible to liquefaction.

5.0 Results

The results of the Safety Factor Assessment are summarized in Table 4 for the North to South Splitter Dike and Table 5 for the East to West Splitter Dike. The outputs of Slope /W are contained in Appendix B of this report.


Table 4: Safety Factor Assessment Summary for the North to South Splitter Dike					
Scenario Description	Calculated Factor of Safety	Required Factor of Safety	Reference to Exhibit	Acceptable (Yes or No)	Commentary
WBAP In Service; EBAP Drained	1.50	1.50	B.1	Yes	
WBAP Drained; EBAP In Service	1.74	1.50	B.2	Yes	
Seismic Loading: WBAP In Service, EBAP Drained	1.09	1.00	B.3	Yes	Horizontal seismic coefficient = 0.145
WBAP in Flood Stage; EBAP Drained	1.47	1.40	B.4	Yes	100-year flood surcharge pool in WBAP.
Rapid Drawdown of East Bottom Ash Pond	1.20	*	B.5	Yes	*= Required Factor of Safety not specified in 40 CFR 257.73 (d) (1) (vii).
Rapid Drawdown of West Bottom Ash Pond	1.56	*	B.6	Yes	*= Required Factor of Safety not specified in 40 CFR 257.73 (d) (1) (vii).

Table 5: Load Cases Analyzed for the East to West Splitter Dike					
Scenario Description	Calculated Factor of Safety	Required Factor of Safety	Reference to Exhibit	Acceptable (Yes or No)	Commentary
EBAP Drained, EWWP In Service	1.52	1.50	B.7	Yes	Routine operations
Seismic- EBAP Drained, EWWP In Service	1.11	1.0	B.8	Yes	Horizontal seismic coefficient = 0.145
EBAP Drained, EWWP at Flood Stage	1.51	1.40	B.9	Yes	100-year flood surcharge pool.
Rapid Drawdown of East Bottom Ash Pond	1.22	*	B.10	Yes	*= Required Factor of Safety not specified in 40 CFR 257.73 (d) (1) (vii).



6.0 Conclusions

Based on the analysis presented in this report, the splitter dikes that impound the East Bottom Ash Pond at the Rockport Plant meet the required factors of safety as required by 40 CFR §257.73(e) for all load cases considered.

Appendix A- Site Map




Rockport Bottom Ash Pond Site Map
 Drawn By: Dan Murphy
 Date: 9/22/2021



Note: Contours as shown were based on LiDAR data made publically available through the Indiana Geospatial Data Portal.
 Locations of borings and monitoring wells are based on historical drawings and should be considered approximate.


Appendix B- Slope /W Outputs

Exhibit B.1




North & South Splitter Dike

Exhibit B.2




North & South Splitter Dike

Exhibit B.3




North & South Splitter Dike

Exhibit B.4




North & South Splitter Dike

Exhibit B.5



North & South Splitter Dike

Exhibit B.6




Name: Embankment Fill Material	Unit Weight: 130 pcf	Cohesion: 50 psf	Phi: 29 °	Cohesion R: 400 psf	Phi R: 19 °	Piezometric Line After Drawdown: 2
Name: Foundation Clay Material	Unit Weight: 123 pcf	Cohesion: 50 psf	Phi: 34 °	Cohesion R: 200 psf	Phi R: 22 °	Piezometric Line After Drawdown: 2
Name: Loose Foundation Sand	Unit Weight: 115 pcf	Cohesion: 0 psf	Phi: 30 °	Cohesion R: 0 psf	Phi R: 0 °	Piezometric Line After Drawdown: 2
Name: Medium Foundation Sand	Unit Weight: 123 pcf	Cohesion: 0 psf	Phi: 33 °	Cohesion R: 0 psf	Phi R: 0 °	Piezometric Line After Drawdown: 2
Name: Riprap	Unit Weight: 150 pcf	Cohesion: 0 psf	Phi: 42 °	Cohesion R: 0 psf	Phi R: 0 °	Piezometric Line After Drawdown: 2

Note: Dimension across both pond bottoms not to scale for clarity in showing profile of the two adjacent bottom ash ponds.

North & South Splitter Dike


Exhibit B.7



East & West Splitter Dike

Exhibit B.8


1.109



East & West Splitter Dike

Exhibit B.9


1.518



East & West Splitter Dike

Exhibit B.10


1.219



Note: Dimension across both pond bottoms not to scale for clarity in showing profile of the two adjacent bottom ash ponds.

East & West Splitter Dike

Appendix C- Historical Geotechnical Information



PROJECT: Rockport Site PROJECT NO W6-1482 BORING: BH-361
 DATE: 3/17/77 DRILLER: G. Powers CREW: J. Hardman/J. Selbe SURFACE ELEV. _____

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	REC
FROM	TO					FROM	TO				
		Topsoil									
	1.0										
1.0		Very stiff brown and gray silty clay		SS	1	5.0	6.5	5	8	11	10
		Very stiff brown and gray silty clay		SS	2	10.0	11.5	8	13	14	9
	13.0										
13.0		Firm brown silty fine sand		SS	3	15.0	16.5	5	5	6	8
	19.0										
19.0		Very loose brown silty fine sand		SS	4	20.0	21.5	1	2	2	1
		Very loose brown silty fine sand		SS	5	25.0	26.5	1	2	2	16
	30.0										
30.0		Very dense dark brown silty fine sand		SS	6	30.0	31.5	6	4	30	16
	34.0										
34.0		Firm brown medium to coarse silty sand		SS	7	35.0	36.5	9	10	13	8
	41.0										
41.0		Firm brown silty fine sand		SS	8	40.0	41.5	9	11	13	16
	44.0										
44.0		Firm brown medium and coarse sand		SS	9	45.0	46.5	8	11	19	16
	48.0										
48.0	51.5	Dense grayish brown silty fine to medium sand		SS	10	50.0	51.5	21	21	24	14
		Boring Terminated @ 51.5 3/17/77									

METHOD OF DRILLING (Check One)
 a. ~~WIGER~~ Rod SIZE A
 b. WASH XX WATER MUD XX
 DRILLING SIZE _____ BIT USED 2-7/8" Side Discharge
 BIT SIZE N/W LENGTH 5.0
 TURBED SAMPLES: NO. _____ SIZE _____
 SAMPLES: NO. _____
 WATER LOSSES, % _____ DEPTH _____
 SPECIAL TESTS (Hrs & Explain) _____

WEATHER Overcast 45 degrees
 NON-DRILLING TIME (Hrs.) _____
 BORING LAYOUT _____ MOVING _____
 HAULING WATER _____ STANDBY _____
 WATER LEVEL: @ _____ DATE _____ TIME _____
 @ _____ DATE _____ TIME _____
 CAVE-IN DEPTH: @ _____ DATE _____ TIME _____

REMARKS: (All remarks should be explained on the back of white copy)
 THIS IS A DRILLER'S LOG AND THE CLASSIFICATIONS HAVE NOT BEEN REVIEWED BY AN ENGINEER

PROJECT: Rockport Site PROJECT NO. W6-1482 BORING: BE-362
 DATE: 3/18/77 DRILLER: G. Powers CREW: J. Hardman/J. Selbe SURFACE ELEV. 392.7

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	REC
FROM	TO					FROM	TO				
0		Topsoil									
	1.2										
1.2	7.5	Very stiff brown and gray fine sandy silty clay		SS	1	5.0	6.5	7	10	12	15
7.5	13.0	Stiff brown fine sandy silt		SS	2	10.0	11.5	4	4	6	16
13.0		Firm brown silty fine sand		SS	3	15.0	16.5	4	5	6	12
	23.5	Firm brown silty fine sand		SS	4	20.0	21.5	4	5	7	4
23.5	29.0	Loose brown silty fine to medium sand		SS	5	25.0	26.5	4	3	4	5
29.0		Firm brown silty fine to medium sand		SS	6	30.0	31.5	4	5	8	10
	37.0	Firm brown silty fine to medium sand		SS	7	35.0	36.5	7	6	10	9
37.0	44.0	Dense brown medium to coarse sand		SS	8	40.0	41.5	12	14	22	10
44.0		Firm brownish gray fine to medium silty sand		SS	9	45.0	46.5	12	12	11	10
51.5		Firm brownish gray fine to medium silty		SS	10	50.0	51.5	8	8	12	9
		Boring Terminated @ 51.5 3/18/77									

METHOD OF DRILLING (Check One)
 a. ~~XXXX~~ Rod SIZE A
 b. WASH XX WATER MUD XX
 BORING SIZE _____ BIT USED _____
 CHANGING: SIZE N/W LENGTH 5'
 UNDISTURBED SAMPLES: NO. _____ SIZE _____
 BAG SAMPLES: NO. _____
 WATER LOSSES _____ DEPTH _____
 SPECIAL TESTS (Hrs & Explain) _____

WEATHER 45 degrees Overcast & windy
 NON-DRILLING TIME (Hrs) _____
 BORING LAYOUT _____ MOVING _____
 HAULING WATER _____ STANDBY _____
 WATER LEVEL: @ _____ DATE _____ TIME _____
 @ _____ DATE _____ TIME _____
 GIVE IN DEPTH: @ _____ DATE _____ TIME _____

REMARKS: (All remarks should be explained on the back of white copy) THIS IS A DRILLER'S LOG AND THE CLASSIFICATIONS HAVE NOT BEEN REVIEWED BY AN ENGINEER

PROJECT: Rockport Site PROJECT NO. W6-1482 BORING: BH-363
 DATE: 3/18/77 DRILLER: G. Powers CREW: J. Hardman/J. Selbe SURFACE ELEV. 392

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	RE
FROM	TO					FROM	TO				
0	0.8	Topsoil									
0.8	8.0	Very stiff brown fine sandy silty clay		SS	1	5.0	6.5	6	9	12	14
8.0		Loose brown silty fine sand		SS	2	10.0	11.5	4	4	5	15
	20.5	Loose brown silty fine sand		SS	3	15.0	16.5	4	5	5	12
20.5	23.5	Firm brown silty fine sand		SS	4	20.0	21.5	2	5	8	10
23.5		Firm brown fine to medium sand		SS	5	25.0	26.5	5	6	6	8
		Firm brown fine to medium sand		SS	6	30.0	31.5	6	7	9	10
	38.0	Firm brown fine to medium sand		SS	7	35.0	26.5	8	8	14	7
38.0		Firm brown medium to coarse sand		SS	8	40.0	41.5	9	10	16	12
		Firm brown medium to coarse sand		SS	9	45.0	46.5	8	14	13	8
	47.0										
47.0	51.5	Firm grayish brown silty fine to medium sand		SS	10	50.0	51.5	7	10	10	12
		Boring Terminated @ 51.5 3/18/77									

METHOD OF DRILLING (Check One)
 a. ~~AUX~~ Rod SIZE A
 b. WASH XX WATER MUD XX
 BORING SIZE _____ BIT USED 2-7/8" Side Discharge
 CA 3: SIZE N/W LENGTH 5.0
 UNDISTURBED SAMPLES: NO. _____ SIZE _____
 JAG SAMPLES: NO. _____
 WATER LOSSES % _____ DEPTH _____
 SPECIAL TESTS (Hrs & Explain) _____

WEATHER 45 degrees Overcast Windy
 NON-DRILLING TIME (Hrs) _____
 BORING LAYOUT _____ MOVING _____
 HAULING WATER _____ STANDBY _____
 WATER LEVEL: @ _____ DATE _____ TIME _____
 @ _____ DATE _____ TIME _____
 CAVE-IN DEPTH: @ _____ DATE _____ TIME _____

REMARKS: (All remarks should be explained on the back of white copy) THIS IS A DRILLER'S LOG AND THE CLASSIFICATIONS HAVE

PROJECT: Rockport Site

PROJECT NO. W6-1482

BORING: BH=364

DATE: 3/15/77

DRILLER: G. Powers

CREW: J. Hardman/J. Selbe

SURFACE ELEV. 389.5

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	REC.
FM	TO					FROM	TO				
0	1.4	Topsoil									
1.4		Stiff brown and gray silty clay traces fine sand		SS	1	5.0	6.5	4	6	7	16
	13.0	Stiff brown and gray silty clay traces fine sand		SS	2	10.0	11.5	3	4	6	12
13.0		Loose brown silty fine sand		SS	3	15.0	16.5	3	4	3	17
	24.0	Loose brown silty fine sand		SS	4	20.0	21.5	3	3	3	8
24.0		Firm brown fine to medium sand		SS	5	25.0	26.5	6	8	8	7
	34.5	Firm brown fine to medium sand		SS	6	30.0	31.5	6	8	9	8
34.5		Firm brown medium to coarse sand		SS	7	35.0	36.5	5	8	10	8
	43.0	Firm brown medium to coarse sand		SS	8	40.0	41.5	5	6	8	7
43.0		Loose brown medium to coarse sand & gravel		SS	9	45.0	46.5	4	3	3	8
	47.0										
47.0	51.5	Firm brown medium to coarse sand traces gravel		SS	10	50.0	51.5	8	9	13	8
		Boring Terminated @ 51.5 3/15/77									

METHOD OF DRILLING (Check One)

a. AUGER Rod SIZE A
 b. WASH XX WATER MUD XX

BIT USED 2-7/8" Side Discharge
 CASING: SIZE NW LENGTH 5'
 UNDISTURBED SAMPLES: NO. SIZE
 BAG SAMPLES: NO.
 WATER LOSSES: DEPTH
 SPECIAL TESTS (List & Explain)

WEATHER 70 degrees clear

NON-DRILLING TIME (Hrs)

BORING LAYOUT MOVING
 HAULING WATER STANDBY
 WATER LEVEL: @ DATE TIME
 @ DATE TIME
 CAVE-IN DEPTH: @ DATE TIME

REMARKS (All remarks should be explained on the back of white copy) THIS IS A DRILLER'S LOG THE CLASSIFICATION

PROJECT: Rockport Site PROJECT NO. W6-1482 BORING: BH=365
 DATE: 3/15/77 DRILLER: G. Powers CREW: J. Hardman/J. Selbe SURFACE ELEV. _____

DEPTH	SOIL STRATA	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	REC.
					FROM	TO				
0	Topsoil									
1.3	Stiff brown and gray silty clay traces		SS	1	5.0	6.5	3	5	9	18
11.0	Stiff brown fine sandy silty tan clay		SS	2	10.0	11.5	4	4	8	18
13.5	Loose brown silty fine sand		SS	3	15.0	16.5	2	3	4	12
19.0	Firm brown fine sand silt traces clay		SS	4	20.0	21.5	3	2	3	14
25.5	Firm brown and gray silty fine sand		SS	5	25.0	26.5	2	5	8	12
28.0	Firm brown silty fine sand		SS	6	30.0	31.5	8	10	10	6
35.5	Firm brown silty medium to coarse sand		SS	7	35.0	36.5	6	11	10	9
40.0	Dense brown silty medium to coarse sand traces gravel		SS	8	40.0	41.5	13	25	25	10
42.0	Firm brown silty medium to coarse sand traces gravel		SS	9	45.0	46.5	10	12	12	8
47.5	Firm gray fine to medium silty sand traces gravel		SS	10	50.0	51.5	8	7	9	8
Boring Terminated @ 51.5 3/15/77										

METHOD OF DRILLING (Check One)
 a. ~~AXXR~~ Rod SIZE A
 b. WASH XX WATER XX MUD XX
 BORING SIZE _____ BIT USED 2-7/8" Side Discharge
 CASING: SIZE NW LENGTH 5.0'
 UNDISTURBED SAMPLES: NO. _____ SIZE _____
 BAG SAMPLES: NO. _____
 WATER LOSSES: % _____ DEPTH _____
 SPECIAL TESTS (Hrs. & Explain) _____

WEATHER 65 degrees clear
 NON-DRILLING TIME (Hrs.) _____
 BORING LAYOUT _____ MOVING _____
 HAULING WATER _____ STANDBY _____
 WATER LEVEL: @ _____ DATE _____ TIME _____
 @ _____ DATE _____ TIME _____
 CAVE-IN DEPTH: @ _____ DATE _____ TIME _____

REMARKS: (All remarks should be explained on the back of white copy) **THIS IS A DRILLER'S LOG! THE CLASSIFICATIONS HAVE NOT BEEN REVIEWED BY AN ENGINEER**

PROJECT: Rockport Site

PROJECT NO. W6-1482

BORING: BH-366

DATE: 3/15/77

DRILLER: G. Powers

CREW: J. Hardman/J. Selbe

SURFACE ELEV.

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	RFC
FROM	TO					FROM	TO				
	1.5	Topsoil									
1.5	9.0	Very stiff brown and gray silty clay traces fine sand		SS	1	5.0	6.5	3	7	14	18
9.0	15.0	Firm brown silty fine sand traces clay		SS	2	10.0	11.5	4	5	8	16
15.0	17.0	Loose brown silty fine sand traces clay		SS	3	15.0	16.5	2	4	6	16
17.0	24.0	loose brown silty fine sand		SS	4	20.0	21.5	4	4	6	8
24.0	33.5	Firm brown fine to medium fine sand		SS	5	25.0	26.5	4	7	12	7
33.5	37.0	Firm brown fine to medium fine sand		SS	6	30.0	31.5	5	8	9	7
37.0	47.5	Firm brown fine to medium sand traces		SS	7	35.0	36.5	5	8	9	6
47.5	51.5	Firm brown medium to coarse silty sand		SS	8	40.0	41.5	8	11	12	7
		Firm brown medium to coarse silty sand		SS	9	45.0	46.5	7	12	16	11
		Firm brown medium to coarse sand some gravel		SS	10	50.0	51.5	7	7	9	8
		Boring Terminated @ 51.5 3/15/77									

TYPE OF DRILLING (Check One)
 Rod SIZE A
 WATER MUD
 BIT USED 2-7/8" Side Discharge
 LENGTH 5.0
 SAMPLES: NO SIZE
 DEPTH

WEATHER 50 degrees overcast
 NON-DRILLING TIME IN
 BORING LAYOUT MOVING
 HAULING WATER STANDBY
 WATER LEVEL: @ DATE TIME
 @ DATE TIME
 CAVE IN DEPTH: @ DATE TIME

REMARKS (All remarks should be explained on the back of white copy) THIS IS A DRILLER'S LOG AND THE CLASSIFICATIONS HAVE NOT BEEN REVIEWED BY AN ENGINEER

PROJECT: Rockport Site PROJECT NO. W6-1482 BORING: Bh-367

DATE: 3/16/77 DRILLER: G. Powers CREW: J. Hardman/J. Selbe SURFACE ELEV. _____

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 5"	2ND 5"	3RD 5"	REC
FROM	TO					FROM	TO				
0		Topsoil									
	1.2										
1.2		Firm brown silty fine sand traces clay		SS	1	5.0	6.5	3	4	7	14
	8.0										
8.0		Loose brown silty fine sand		SS	2	10.0	11.5	3	3	5	12
		Loose brown silty fine sand		SS	3	15.0	16.5	3	3	4	10
		Loose brown silty fine sand		SS	4	20.0	21.5	3	5	5	8
	23.0										
23.0		Firm brown silty fine to medium sand		SS	5	25.0	26.5	7	10	14	7
		Firm brown silty fine to medium sand		SS	6	30.0	31.5	7	8	9	6
		Firm brown silty fine to medium sand		SS	7	35.0	36.5	5	7	10	6
		Firm brown silty fine to medium sand		SS	8	40.0	41.5	8	11	14	6
	44.0										
44.0		Firm brown silty medium to coarse sand		SS	9	45.0	46.5	10	15	13	8
		Firm brown silty medium to coarse sand		SS	10	50.0	51.5	7	12	11	10
	51.5										
		Boring Terminated @ 51.5									

METHOD OF DRILLING (Check One)
 a. ~~XXX~~ Rod SIZE A
 b. WASH XX WATER XX MUD XX
 DRILLING SIZE _____ BIT USED 2-7/8" Side Discharge
 CASINGS: SIZE NW LENGTH 5.0'
 UNL TURBED SAMPLES: NO. _____ SIZE _____
 TAG SAMPLES: NO. _____
 WATER LOSSES % _____ DEPTH _____
 SPECIAL TESTS (Hrs & Explain) _____

WEATHER Clear 60 degrees
 NON-DRILLING TIME (Hrs.) _____
 BORING LAYOUT _____ MOVING _____
 HAULING WATER _____ STANDBY _____
 WATER LEVEL: @ _____ DATE _____ TIME _____
 @ _____ DATE _____ TIME _____
 CAVE-IN DEPTH: @ _____ DATE _____ TIME _____

REMARKS: (All remarks should be explained on the back of white copy) THIS IS A DRILLER'S LOG AND THE CLASSIFICATIONS HAVE NOT BEEN REVIEWED BY AN ENGINEER

PROJECT: Rockport Site

PROJECT NO. W6-1482

BORING: BH-368

DATE: 3/16/77

DRILLER: G. Powers

CREW: J. Hardman/J. Selbe

SURFACE ELEV. 392.3

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	REC
FROM	TO					FROM	TO				
J		Topsoil									
	0.7										
0.7		Very stiff brown silty clay		SS	1	5.0	6.5	3	12	15	18
	9.0										
9.0		Firm brown silty fine sand		SS	2	10.0	11.5	7	7	8	14
		Firm brown silty fine sand		SS	3	15.0	16.5	5	5	6	9
		Firm brown silty fine sand		SS	4	20.0	21.5	5	6	8	8
	24.0										
24.0		Firm brown silty fine to medium sand		SS	5	25.0	26.5	8	10	13	6
		Firm brown silty fine to medium sand		SS	6	30.0	31.5	5	7	7	7
	33.0										
33.0		Firm brown medium to coarse sand		SS	7	35.0	36.5	6	6	8	5
	37.5										
37.5		Firm brown fine to medium silty sand		SS	8	40.0	41.5	5	7	8	6
	44.0										
44.0		Firm brown medium to coarse sand		SS	9	45.0	46.5	5	10	13	9
	51.5										
51.5		Firm brown medium to coarse sand		SS	10	50.0	51.5	10	12	12	12
		Boring Terminated @ 51.5'									

METHOD OF DRILLING (Check One)
 a. ~~XXXX~~ Rod SIZE A
 b. WASH XX WATER MUD XX
 BORE SIZE BIT USED 2-7/8" Side Discharge
 CA G: SIZE NW LENGTH 5.0'
 UNDISTURBED SAMPLES: NO. SIZE
 TAG SAMPLES: NO.
 WATER LOSSES, % DEPTH
 SPECIAL TESTS (Hrs. & Explain)

WEATHER Clear 45 degrees
 NON-DRILLING TIME (Hrs.)
 BORING LAYOUT MOVING
 HAULING WATER STANDBY
 WATER LEVEL: @ DATE TIME
 @ DATE TIME
 CAVE-IN DEPTH: @ DATE TIME

REMARKS: (All remarks should be explained on the back of white copy) THIS IS A DRILLER'S LOG AND THE CLASSIFICATIONS HAVE NO BEEN REVIEWED BY ALL ENGINEERS

PROJECT: Rockport Site

PROJECT NO. W6-1482

BORING: BH-369

DATE: 3/18/77 DRILLER: R. Stevens

CREW: B. Blackford/D. Woodens SURFACE ELEV. 394.3

DEPTH		SOIL STRATA SOIL DESCRIPTION AND REMARKS	TIME	TYPE	NO.	DEPTH		FIRST 6"	2ND 6"	3RD 6"	REC.
FROM	TO					FROM	TO				
0	12"	Topsoil									
	9.0	Very stiff brown and tan clay		SS	1	5	6.5	8	12	15	18
9.0	12.7	Loose brown very silty fine sand		SS	2	10	11.5	3	3	4	12
12.7	18.0	Firm brown medium sand		SS	3	15	16.5	5	6	7	5
18.0	22.1	Loose gray and brown silty fine to medium sand		SS	4	20	21.5	3	4	5	6
22.1	28.5	Firm brown medium sand		SS	5	25	26.5	9	10	10	6
28.5	32.0	Loose brown medium sand w/traces fine gravel		SS	6	30	31.5	3	4	4	5
32.0	44.0	Firm brown medium to coarse sand		SS	7	35	36.5	7	10	16	8
	44.0	Firm brown medium to coarse sand		SS	8	40	41.5	10	11	13	7
44.0	47.5	Dense brown medium to coarse sand		SS	9	45	46.5	11	15	18	10
47.5		Dense brown medium to coarse sand w/fine gravel		SS	10	50	51.5	11	19	26	10
Boring Terminated @ 51.5'											

METHOD OF DRILLING (Check One)

a AIRLIFT Rod SIZE A

b WASH XX WATER MUD XX

BORING SIZE 2-7/8" BIT USED 2-7/8" Side Discharge

CUTTING: SIZE NW 5" LENGTH

UNDISTURBED SAMPLES: NO. SIZE

TAG SAMPLES: NO.

WATER LOSSES: % DEPTH

SPECIAL TESTS (Hrs. & Explain)

WEATHER Cloudy 50 degrees

NON-DRILLING TIME (Hrs.)

BORING LAYOUT MOVING



HAULING WATER STANDBY

WATER LEVEL: @ DATE TIME

@ DATE TIME

CAVE-IN DEPTH: @ DATE TIME

REMARKS: (All remarks should be explained on the back of white copy) THIS IS A DRILLER'S LOG AND THE CLASSIFICATIONS HAVE NOT BEEN REVIEWED BY AN ENGINEER



NOTE
 THE AERIAL TOPOGRAPHY WAS OBTAINED FROM HENDERSON AERIAL SURVEYS INC., DATED 11/10/2007.

STATE ROUTE 231

LEGEND
 B-1 SOIL BORING

REV.	DATE	BY	DESCRIPTION

Terracon
 Consulting Engineers and Scientists
 800 MORRISON ROAD
 COLUMBUS, OHIO 43220
 PH. (614) 863-3113 FAX. (614) 863-0475

SITE PLAN
 ROCKPORT PLANT
 AMERICAN ELECTRIC POWER
 ROCKPORT PLANT BOTTOM ASH POND COMPLEX
 ROCKPORT

EXHIBIT A-3

DESIGNED BY:	BMY
DRAWN BY:	DAB
APPROV. BY:	MSF
SCALE:	1"=300'
DATE:	10/15/15
JOB NO.:	N4155126
ACAD NO.:	PSET2
SHEET NO.:	1 OF 1

BORING LOG NO. B-1

PROJECT: Rockport Plant Impoundment Certification

CLIENT: American Electric Power
Columbus, Ohio

SITE:

Rockport, Indiana

GRAPHIC LOG	LOCATION See Exhibit A-3 Latitude: 37.918487° Longitude: -87.039045° Surface Elev.: 389.7 (Ft.)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (in.)	FIELD TEST RESULTS	LABORATORY TORVANE/HP (tsf)	ATTERBERG LIMITS
	DEPTH	ELEVATION (Ft.)						LL-PL-PI
	TOPSOIL (3")	0.3						
	SANDY FAT CLAY (CH) , trace gravel, brown, stiff	389.5			14	5-3-4-4 N=7	3.0 (HP)	
					12	5-4-4-5 N=8	1.0 (HP)	69-26-43
					18			
	LEAN CLAY (CL) , trace sand, gray and brown, stiff	383.5			24	2-3-4-5 N=7	2.0 (HP)	
					24			42-22-20
					24	2-3-5-6 N=8	1.25 (HP)	
					24	2-4-5-6 N=9	2.0 (HP)	
					24			28-18-10
			▽		24	2-3-3-3 N=6	1.25 (HP)	
	SANDY SILT (ML) , brown, loose	372			18	2-4-4-4 N=8		
	POORLY GRADED SAND (SP) , brown, loose	371						
	POORLY GRADED SAND (SP) , trace gravel, brown, medium dense	366.5			24	3-7-8-9 N=15		

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method:
3.25" Hollow Stem Auger

See Exhibit A-1 for description of field procedures

Notes:

Abandonment Method:
Boring backfilled with cement/bentonite grout upon completion.

See Appendix B for description of laboratory procedures and additional data (if any).
See Appendix C for explanation of symbols and abbreviations.

WATER LEVEL OBSERVATIONS

▽ Water encountered at 17.5 feet while sampling



Boring Started: 9/3/2015

Boring Completed: 9/4/2015

Drill Rig: Track

Driller: Davis

Project No.: N4155126

Exhibit: A-4

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL ROCKPORT CCR BORINGS.GPJ TERRACON2015.GDT 10/16/15

BORING LOG NO. B-1

PROJECT: Rockport Plant Impoundment Certification

CLIENT: American Electric Power
Columbus, Ohio

SITE:

Rockport, Indiana

GRAPHIC LOG	LOCATION See Exhibit A-3 Latitude: 37.918487° Longitude: -87.039045°	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (in.)	FIELD TEST RESULTS	LABORATORY TORVANE/HP (tsf)	ATTERBERG LIMITS
	Surface Elev.: 389.7 (Ft.) ELEVATION (Ft.)							LL-PL-PI
	POORLY GRADED SAND (SP) , trace gravel, brown, medium dense <i>(continued)</i>	30		24		4-5-5-5 N=10		
	POORLY GRADED SAND (SP) , trace gravel, brown, medium dense	35.0		24		4-6-7-7 N=13		
	Boring Terminated at 35 Feet	35						

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method:
3.25" Hollow Stem Auger

See Exhibit A-1 for description of field procedures

Notes:

Abandonment Method:
Boring backfilled with cement/bentonite grout upon completion.

See Appendix B for description of laboratory procedures and additional data (if any).

See Appendix C for explanation of symbols and abbreviations.

WATER LEVEL OBSERVATIONS

∇ Water encountered at 17.5 feet while sampling



Boring Started: 9/3/2015

Boring Completed: 9/4/2015

Drill Rig: Track

Driller: Davis

Project No.: N4155126

Exhibit: A-4

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL ROCKPORT CCR BORINGS.GPJ TERRACON2015.GDT 10/16/15

BORING LOG NO. B-2

PROJECT: Rockport Plant Impoundment Certification

CLIENT: American Electric Power
Columbus, Ohio

SITE:

Rockport, Indiana

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL. ROCKPORT CCR BORINGS.GPJ TERRACON2015.GDT 10/16/15

GRAPHIC LOG	LOCATION See Exhibit A-3 Latitude: 37.918457° Longitude: -87.038804° Surface Elev.: 397.4 (Ft.)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (in.)	FIELD TEST RESULTS	LABORATORY TORVANE/HP (tsf)	ATTERBERG LIMITS
	DEPTH	ELEVATION (Ft.)						LL-PL-PI
0.1	TOPSOIL (1")	397.9						
	FILL - LEAN CLAY (CL) , trace sand, brown				19	6-10-14-16 N=24		28-15-13
4.0		393.5			4	15-12-10-10 N=22		
	FILL - SANDY SILT (ML) , brown				24			19-16-3
6.0		391.5			23	2-3-5-6 N=8		
	FILL - SANDY LEAN CLAY (CL) , trace gravel, gray and brown 5" poorly graded sand seam from 6-6.4'				24	3-7-10-17 N=17	3.25 (HP)	
8.0		389.5			24			30-21-9
	LEAN CLAY (CL) , trace sand, gray, very stiff							
12.0		385.5			24	3-4-6-8 N=10	1.5 (HP)	
	LEAN CLAY (CL) , brown, stiff				24	3-5-7-9 N=12	1.75 (HP)	
14.0		383.5			17	6-10-12-14 N=22	2.75 (HP)	35-15-20
	SANDY LEAN CLAY (CL) , trace gravel, gray and orange, stiff				24			
20.8		376.5			24	3-4-4-5 N=8		
	CLAYEY SAND (SC) , brown, loose				23	3-3-4-5 N=7		
22.7		374.5			21	2-3-4-4		
	POORLY GRADED SAND WITH SILT (SP-SM) , trace gravel, brown, loose							

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method:
3.25" Hollow Stem Auger

See Exhibit A-1 for description of field procedures

Notes:

A monitoring well was installed in an offset hole approximately 10 feet south of the boring.

Abandonment Method:
Boring backfilled with cement/bentonite grout upon completion.

See Appendix B for description of laboratory procedures and additional data (if any).
See Appendix C for explanation of symbols and abbreviations.

WATER LEVEL OBSERVATIONS

Water encountered at 25.1 feet while sampling



Boring Started: 9/4/2015

Boring Completed: 9/4/2015

Drill Rig: Track

Driller: Davis

Project No.: N4155126

Exhibit: A-5

BORING LOG NO. B-2

PROJECT: Rockport Plant Impoundment Certification

CLIENT: American Electric Power
Columbus, Ohio

SITE:

Rockport, Indiana

GRAPHIC LOG	LOCATION See Exhibit A-3 Latitude: 37.918457° Longitude: -87.038804°	DEPTH (Ft.)	ELEVATION (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (in.)	FIELD TEST RESULTS	LABORATORY TORVANE/HP (tsf)	ATTERBERG LIMITS
	LL-PL-PI								
		25.5	372	▽	X	21	N=7		
POORLY GRADED SAND WITH SILT (SP-SM), trace gravel, brown, loose to medium dense					X	24	6-6-5-4 N=11		
					X	18	2-2-5-3 N=7		
					X	24	2-3-4-4 N=7		
		32.5	365		X	19	1-2-2-2 N=4		
SILTY SAND (SM), brown, loose					X	8	2-3-3-4 N=6		
	3" clay seam at 33.7'	34.0	363.5		X	17	2-2-2-4 N=4		
SILTY SAND (SM), trace gravel, brown, loose					X	1	3-4-5-5 N=9		
					X	9	3-5-6-5 N=11		
POORLY GRADED SAND (SP), trace gravel, brown, loose to medium dense		38.0	359.5		X	6	4-6-9-12 N=15		
					X				
POORLY GRADED SAND (SP), trace gravel, brown, medium dense		42.0	355.5		X				
		44.0	353.5		X				
Boring Terminated at 44 Feet									

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method:
3.25" Hollow Stem Auger

See Exhibit A-1 for description of field procedures

Notes:

Abandonment Method:
Boring backfilled with cement/bentonite grout upon completion.

See Appendix B for description of laboratory procedures and additional data (if any).

See Appendix C for explanation of symbols and abbreviations.

WATER LEVEL OBSERVATIONS

▽ Water encountered at 25.1 feet while sampling



Boring Started: 9/4/2015

Boring Completed: 9/4/2015

Drill Rig: Track


Driller: Davis

Project No.: N4155126

Exhibit: A-5

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL ROCKPORT CCR BORINGS.GPJ TERRACON2015.GDT 10/16/15

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	4.2	31.0	0.7	1.7	14.7	47.7

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8	100.0		
#4	95.8		
#10	64.8		
#20	64.7		
#40	64.1		
#100	63.1		
#200	62.4		
0.0240 mm.	57.5		
0.0155 mm.	56.0		
0.0092 mm.	53.3		
0.0067 mm.	50.1		
0.0049 mm.	47.5		
0.0029 mm.	43.8		

Soil Description

Brown SANDY FAT CLAY, trace gravel

Atterberg Limits

PL= 26 LL= 69 PI= 43

Coefficients

D₉₀= 3.9559 D₈₅= 3.4817 D₆₀= 0.0406
D₅₀= 0.0066 D₃₀= D₁₅=
D₁₀= C_u= C_c=

Classification

USCS= CH AASHTO= A-7-6(25)

Remarks

F.M.=1.79

* (no specification provided)


Source of Sample: B-1 Depth: 2.0'-4.0'
Sample Number: S-2

Date: 9-21-15

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-2
--	--

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.0	0.3	12.3	83.1	1.4	2.9

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#4	100.0		
#10	99.7		
#20	98.6		
#40	87.4		
#100	7.7		
#200	4.3		
0.0357 mm.	4.3		
0.0227 mm.	3.3		
0.0131 mm.	3.3		
0.0093 mm.	3.3		
0.0066 mm.	3.3		
0.0038 mm.	2.3		

Soil Description

Brown poorly graded SAND

Atterberg Limits

PL= NP LL= NP PI= NP

Coefficients

D₉₀= 0.4785 D₈₅= 0.4068 D₆₀= 0.2938
D₅₀= 0.2631 D₃₀= 0.2102 D₁₅= 0.1721
D₁₀= 0.1577 C_u= 1.86 C_c= 0.95

Classification

USCS= SP AASHTO= A-3

Remarks

F.M.=1.37


* (no specification provided)

Source of Sample: B-1 Depth: 18.0'-20.0' Date: 9-21-15
Sample Number: S-7

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-4
--	--

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.2	1.6	63.7	32.8	0.4	1.3

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8	100.0		
#4	99.8		
#10	98.2		
#20	90.4		
#40	34.5		
#100	2.4		
#200	1.7		
0.0362 mm.	1.8		
0.0229 mm.	1.3		
0.0132 mm.	1.3		
0.0094 mm.	1.3		
0.0066 mm.	1.3		
0.0038 mm.	1.3		

Soil Description

Brown poorly graded SAND, trace gravel

Atterberg Limits

PL= NP LL= NP PI= NP

Coefficients

D₉₀= 0.8432 D₈₅= 0.7776 D₆₀= 0.5735
 D₅₀= 0.5129 D₃₀= 0.3986 D₁₅= 0.2992
 D₁₀= 0.2576 C_u= 2.23 C_c= 1.08

Classification

USCS= SP AASHTO= A-1-b

Remarks

F.M.=2.26


* (no specification provided)

Source of Sample: B-1 Depth: 28.0'-30.0' Date: 9-21-15
 Sample Number: S-9

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-5
--	---

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	2.9	21.1	60.5	12.9	2.6	

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8	100.0		
#4	97.1		
#10	76.0		
#20	34.3		
#40	15.5		
#100	3.8		
#200	2.6		

Soil Description

Brown poorly graded SAND, trace gravel

Atterberg Limits

PL= NP LL= NP PI= NP

Coefficients

D ₉₀ = 3.0772	D ₈₅ = 2.5603	D ₆₀ = 1.4351
D ₅₀ = 1.1849	D ₃₀ = 0.7595	D ₁₅ = 0.4140
D ₁₀ = 0.2999	C _u = 4.79	C _c = 1.34

Classification

USCS= SP AASHTO= A-1-b

Remarks

F.M.=3.34


* (no specification provided)

Source of Sample: B-1 Depth: 33.0'-35.0' Date: 9-21-15
 Sample Number: S-10

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-6
--	---

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.4	14.9	0.7	14.9	39.8	29.3

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8	100.0		
#4	99.6		
#10	84.7		
#20	84.5		
#40	84.0		
#100	76.6		
#200	69.1		
0.0279 mm.	55.0		
0.0185 mm.	47.4		
0.0111 mm.	40.5		
0.0081 mm.	35.0		
0.0058 mm.	30.9		
0.0034 mm.	26.1		

Soil Description

FILL: Brown sandy lean clay, trace gravel

Atterberg Limits
 PL= 15 LL= 28 PI= 13

Coefficients
 D₉₀= 2.7745 D₈₅= 2.0607 D₆₀= 0.0375
 D₅₀= 0.0215 D₃₀= 0.0054 D₁₅=
 D₁₀= C_u= C_c=

Classification
 USCS= CL AASHTO= A-6(6)

Remarks
 F.M.=0.86



* (no specification provided)

Source of Sample: B-2 Depth: 0.0'-2.0' Date: 9-21-15
 Sample Number: S-1

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126	Exhibit B-7
--	--	-------------

Tested By: DS Checked By: AM

LIQUID AND PLASTIC LIMITS TEST REPORT



MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
● FILL: Brown sandy lean clay, trace gravel	28	15	13	84.0	69.1	CL

Project No. N4155126 **Client:** American Electric Power

Project: Rockport Plant Impoundment Certification

Source of Sample: B-2 **Depth:** 0.0'-2.0'
Sample Number: S-1

Remarks:

● Date: 9-21-15


TERRACON CONSULTANTS, INC.

Columbus, Ohio

Exhibit B-8

Tested By: DS **Checked By:** AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	14.2	0.5	6.1	2.0	13.7	33.3	30.2

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
1.5	100.0		
1.0	85.8		
3/4	85.8		
1/2	85.8		
3/8	85.8		
#4	85.3		
#10	79.2		
#20	78.4		
#40	77.2		
#100	69.6		
#200	63.5		
0.0275 mm.	52.9		
0.0181 mm.	47.2		
0.0109 mm.	40.8		
0.0079 mm.	36.3		
0.0057 mm.	31.8		
0.0034 mm.	26.7		

Soil Description

Gray and orange SANDY LEAN CLAY, trace gravel

Atterberg Limits

PL= 15 LL= 35 PI= 20

Coefficients

D₉₀= 30.0206 D₈₅= 4.4748 D₆₀= 0.0517
D₅₀= 0.0223 D₃₀= 0.0049 D₁₅=
D₁₀= C_u= C_c=

Classification

USCS= CL AASHTO= A-6(10)

Remarks

F.M.=1.61


* (no specification provided)

Source of Sample: B-2 Depth: 16.0'-18.0' Date: 9-21-15
Sample Number: S-7

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-9
--	--

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.2	1.0	15.0	78.3	0.8	4.7

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8	100.0		
#4	99.8		
#10	98.8		
#20	96.2		
#40	83.8		
#100	8.2		
#200	5.5		
0.0355 mm.	5.0		
0.0224 mm.	5.0		
0.0130 mm.	5.0		
0.0092 mm.	5.0		
0.0065 mm.	5.0		
0.0038 mm.	4.1		

Soil Description

Brown poorly graded SAND with silt, trace gravel

Atterberg Limits
 PL= NP LL= NP PI= NP

Coefficients

D ₉₀ = 0.4948	D ₈₅ = 0.4358	D ₆₀ = 0.3031
D ₅₀ = 0.2696	D ₃₀ = 0.2128	D ₁₅ = 0.1722
D ₁₀ = 0.1566	C _u = 1.94	C _c = 0.95

Classification
 USCS= SP-SM AASHTO= A-3

Remarks
 F.M.=1.42


* (no specification provided)

Source of Sample: B-2 Depth: 22.0'-24.0' Date: 9-21-15
 Sample Number: S-9

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126	Exhibit B-11
--	--	--------------

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	1.2	9.5	47.4	36.0	5.9	

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8	100.0		
#4	98.8		
#10	89.3		
#20	75.1		
#40	41.9		
#100	8.4		
#200	5.9		

Soil Description

Brown poorly graded SAND with silt, trace gravel

Atterberg Limits

PL= NP LL= NP PI= NP

Coefficients

D₉₀= 2.1334 D₈₅= 1.3167 D₆₀= 0.6037
 D₅₀= 0.4980 D₃₀= 0.3271 D₁₅= 0.2100
 D₁₀= 0.1667 C_u= 3.62 C_c= 1.06

Classification

USCS= SP-SM AASHTO= A-1-b

Remarks

F.M.=2.32


* (no specification provided)

Source of Sample: B-2 Depth: 28.0'-30.0' Date: 9-21-15
 Sample Number: S-12

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-12
--	--

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.0	0.0	0.2	56.2	43.6	

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#10	100.0		
#20	100.0		
#40	99.8		
#100	88.7		
#200	43.6		

Soil Description

Brown SILTY SAND

Atterberg Limits

PL= NP LL= NP PI= NP

Coefficients

D₉₀= 0.1621 D₈₅= 0.1384 D₆₀= 0.0932
 D₅₀= 0.0815 D₃₀= D₁₅=
 D₁₀= C_u= C_c=

Classification

USCS= SM AASHTO= A-4(0)

Remarks

F.M.=0.14

* (no specification provided)


Source of Sample: B-2 Depth: 32.0'-33.7'
 Sample Number: S-14A

Date: 9-21-15

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-13
--	---

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	1.0	3.4	17.4	47.2	13.5	17.5

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8	100.0		
#4	99.0		
#10	95.6		
#20	89.7		
#40	78.2		
#100	50.7		
#200	31.0		
0.0328 mm.	28.0		
0.0210 mm.	25.7		
0.0121 mm.	25.0		
0.0087 mm.	21.9		
0.0062 mm.	18.9		
0.0036 mm.	15.8		

Soil Description
Brown SILTY SAND, trace gravel

Atterberg Limits
 PL= NP LL= NP PI= NP

Coefficients
 D₉₀= 0.8715 D₈₅= 0.6088 D₆₀= 0.2033
 D₅₀= 0.1468 D₃₀= 0.0537 D₁₅=
 D₁₀= C_u= C_c=

Classification
 USCS= SM AASHTO= A-2-4(0)

Remarks
 F.M.=1.06


* (no specification provided)

Source of Sample: B-2 Depth: 34.0'-36.0' Date: 9-21-15
 Sample Number: S-15

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126	Exhibit B-14
--	--	--------------

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	11.0	12.9	45.3	28.3	2.5	

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/4	100.0		
1/2	97.9		
3/8	97.5		
#4	89.0		
#10	76.1		
#20	60.7		
#40	30.8		
#100	4.1		
#200	2.5		

Soil Description

Brown poorly graded SAND, trace gravel

Atterberg Limits

PL= NP LL= NP PI= NP

Coefficients

D₉₀= 5.0561 D₈₅= 3.7126 D₆₀= 0.8336
D₅₀= 0.6494 D₃₀= 0.4167 D₁₅= 0.2704
D₁₀= 0.2206 C_u= 3.78 C_c= 0.94

Classification

USCS= SP AASHTO= A-1-b

Remarks

F.M.=2.98


* (no specification provided)

Source of Sample: B-2 Depth: 42.0'-44.0' Date: 9-21-15
Sample Number: S-19

TERRACON CONSULTANTS, INC. Columbus, Ohio	Client: American Electric Power Project: Rockport Plant Impoundment Certification Project No: N4155126 Exhibit B-15
--	---

Tested By: DS Checked By: AM

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.1	0.2	1.5	7.2	55.1	35.9

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
.375	100.0		
#4	99.9		
#10	99.7		
#20	99.2		
#40	98.2		
#60	96.4		
#140	92.6		
#200	91.0		

Material Description

BROWN GRAY LEAN CLAY

PL= 22 **Atterberg Limits** LL= 42 PI= 20

Coefficients

D₉₀= 0.0705 D₈₅= 0.0568 D₆₀= 0.0115
D₅₀= 0.0062 D₃₀= D₁₅=
D₁₀= C_u= C_c=

USCS= CL **Classification** AASHTO= A-7-6(19)

Remarks



* (no specification provided)

Source of Sample: B-1 Depth: 8-10'
Sample Number: ST-2

Date: 9-28-15

<h2 style="margin: 0;">Terracon, Inc.</h2> <p style="margin: 0;">Cincinnati, Ohio</p>	<p>Client: AEP</p> <p>Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION</p> <p>Project No: N4155126</p>
<p>Exhibit 7353</p>	

Tested By: DR Checked By: GS



Sample No.	1	2	3	
Initial	Water Content, %	25.2	28.6	27.0
	Dry Density, pcf	99.0	94.6	97.1
	Saturation, %	96.6	98.7	98.9
	Void Ratio	0.7033	0.7825	0.7364
	Diameter, in.	2.867	2.885	2.862
	Height, in.	5.748	5.717	5.757
At Test	Water Content, %	25.2	27.8	24.9
	Dry Density, pcf	100.4	96.3	100.7
	Saturation, %	100.0	100.0	100.0
	Void Ratio	0.6794	0.7499	0.6736
	Diameter, in.	2.854	2.867	2.827
	Height, in.	5.721	5.682	5.687
Strain rate, in./min.	0.000	0.000	0.000	
Back Pressure, tsf	3.600	3.600	3.600	
Cell Pressure, tsf	3.852	4.097	5.602	
Fail. Stress, tsf	Total Pore Pr., tsf	0.388	1.252	2.652
	Ult. Stress, tsf	3.686	3.802	4.615
$\bar{\sigma}_1$ Failure, tsf	Total Pore Pr., tsf	0.554	1.547	3.638
	$\bar{\sigma}_3$ Failure, tsf	0.166	0.295	0.986

Type of Test:

CU with Pore Pressures

Sample Type: ST

Description: BROWN GRAY LEAN CLAY

LL= 42 PL= 22 PI= 20

Assumed Specific Gravity= 2.70

Remarks:

Exhibit 7353

Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-1 **Depth:** 8-10'

Sample Number: ST-2

Proj. No.: N4155126

Date Sampled: 9-28-15






TRIAXIAL SHEAR TEST REPORT

Terracon, Inc.
Cincinnati, Ohio

Tested By: FCE

Checked By: GS

Exhibit B-18



Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-1

Depth: 8-10'

Sample Number: ST-2

Project No.: N4155126


Exhibit _____

Terracon, Inc.

Tested By: FCE

Checked By: GS

Particle Size Distribution Report



% +3"	% Gravel	% Sand	% Silt	% Clay
0.0	0.0	9.7	58.1	32.2

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#4	100.0		
#10	99.9		
#20	99.5		
#40	98.9		
#60	98.1		
#140	94.3		
#200	90.3		

Material Description

BROWN GRAY LEAN CLAY

Atterberg Limits

PL= 18 LL= 28 PI= 10

Coefficients

D₉₀= 0.0742 D₈₅= 0.0645 D₆₀= 0.0227
D₅₀= 0.0152 D₃₀= 0.0038 D₁₅=
D₁₀= C_u= C_c=

Classification

USCS= CL AASHTO= A-4(8)

Remarks

* (no specification provided)


Source of Sample: B-1 Depth: 14-16'
Sample Number: ST-3

Date: 10-05-15

<h2 style="margin: 0;">Terracon, Inc.</h2> <p style="margin: 0;">Cincinnati, Ohio</p>	<p>Client: AEP</p> <p>Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION</p> <p>Project No: N4155126</p> <p style="text-align: right;">Exhibit</p>
---	---

Tested By: JB Checked By: GS

LIQUID AND PLASTIC LIMITS TEST REPORT



MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
● BROWN GRAY LEAN CLAY	28	18	10	98.9	90.3	CL



Project No. N4155126 Client: AEP
 Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

● Source of Sample: B-1 Depth: 14-16' Sample Number: ST-3

Remarks:
 ● MC - 22.5%

Terracon, Inc.

Cincinnati, Ohio



Sample No.	1	
Initial	Water Content, %	22.5
	Dry Density, pcf	104.7
	Saturation, %	99.5
	Void Ratio	0.6095
	Diameter, in.	2.860
At Test	Height, in.	5.734
	Water Content, %	22.9
	Dry Density, pcf	104.7
	Saturation, %	101.4
	Void Ratio	0.6095
	Diameter, in.	2.860
	Height, in.	5.734
	Strain rate, in./min.	0.057
	Back Pressure, tsf	0.000
	Cell Pressure, tsf	0.144
Fail. Stress, tsf	2.528	
Ult. Stress, tsf		
σ_1 Failure, tsf	2.672	
σ_3 Failure, tsf	0.144	

Type of Test:
Unconsolidated Undrained

Sample Type: ST

Description: BROWN GRAY LEAN CLAY

LL= 28 PL= 18 PI= 10

Assumed Specific Gravity= 2.70

Remarks:

Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-1 **Depth:** 14-16'

Sample Number: ST-3






Proj. No.: N4155126 **Date Sampled:** 10-05-15

Exhibit 7354

TRIAXIAL SHEAR TEST REPORT

Terracon, Inc.
Cincinnati, Ohio

Tested By: FCE Checked By: GS



Stress Paths: o indicates peak + indicates end

Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-1

Depth: 14-16'

Sample Number: ST-3

Project No.: N4155126


Exhibit _____

Terracon, Inc.

Tested By: FCE

Checked By: GS

Particle Size Distribution Report



% +3"	% Gravel	% Sand	% Silt	% Clay
0.0	0.0	42.7	32.7	24.6

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
.375	100.0		
#4	100.0		
#10	99.8		
#20	99.2		
#40	97.8		
#60	92.1		
#140	62.7		
#200	57.3		

Material Description

BROWN SANDY SILT

Atterberg Limits
 PL= 16 LL= 19 PI= 3

Coefficients
 D₉₀= 0.2316 D₈₅= 0.1995 D₆₀= 0.0905
 D₅₀= 0.0538 D₃₀= 0.0094 D₁₅=
 D₁₀= C_u= C_c=

Classification
 USCS= ML AASHTO= A-4(0)

Remarks

* (no specification provided)


Source of Sample: B-2 Depth: 4-6'
 Sample Number: ST-1

Date: 10-5-15

<h2 style="margin: 0;">Terracon, Inc.</h2> <p style="margin: 0;">Cincinnati, Ohio</p>	Client: AEP Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION Project No: N4155126
Exhibit	

Tested By: JB Checked By: GS

LIQUID AND PLASTIC LIMITS TEST REPORT



MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
• BROWN SANDY SILT	19	16	3	97.8	57.3	ML



Project No. N4155126 **Client:** AEP
Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION
 • **Source of Sample:** B-2 **Depth:** 4-6' **Sample Number:** ST-1

Terracon, Inc.
 Cincinnati, Ohio

Remarks:

Exhibit

Tested By: VD **Checked By:** GS



Sample No.		1	2
Initial	Water Content, %	15.6	17.3
	Dry Density, pcf	110.4	114.3
	Saturation, %	80.0	98.5
	Void Ratio	0.5262	0.4741
	Diameter, in.	2.853	2.844
	Height, in.	5.704	5.702
At Test	Water Content, %	18.1	15.8
	Dry Density, pcf	113.2	118.0
	Saturation, %	100.0	100.0
	Void Ratio	0.4887	0.4279
	Diameter, in.	2.829	2.814
	Height, in.	5.657	5.642
Strain rate, in./min.	0.001	0.001	
Back Pressure, tsf	3.600	3.600	
Cell Pressure, tsf	3.852	7.596	
Fail. Stress, tsf	0.883	4.618	
Total Pore Pr., tsf	3.607	5.378	
Ult. Stress, tsf			
Total Pore Pr., tsf			
$\bar{\sigma}_1$ Failure, tsf	1.127	6.836	
$\bar{\sigma}_3$ Failure, tsf	0.245	2.218	

Type of Test:

CU with Pore Pressures

Sample Type: ST

Description: BROWN SANDY SILT

LL= 19 PL= 16 PI= 3

Assumed Specific Gravity= 2.70

Remarks:

Exhibit 7355

Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-2 **Depth:** 4-6'






Sample Number: ST-1

Proj. No.: N4155126

Date Sampled: 10-5-15

TRIAXIAL SHEAR TEST REPORT

Terracon, Inc.
Cincinnati, Ohio



Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-2

Depth: 4-6'

Sample Number: ST-1

Project No.: N4155126


Exhibit _____

Terracon, Inc.

Tested By: FCE

Checked By: GS

Particle Size Distribution Report



% +3"	% Gravel	% Sand	% Silt	% Clay
0.0	0.0	7.0	48.5	44.5

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#4	100.0		
#10	99.7		
#20	99.1		
#40	98.1		
#60	97.3		
#140	94.2		
#200	93.0		

Material Description

GRAY LEAN CLAY

PL= 21	Atterberg Limits	LL= 30	PI= 9
	Coefficients		
D ₉₀ = 0.0662	D ₈₅ = 0.0568	D ₆₀ = 0.0159	
D ₅₀ = 0.0078	D ₃₀ =	D ₁₅ =	
D ₁₀ =	C _u =	C _c =	
Classification			
USCS= CL		AASHTO= A-4(8)	
Remarks			

* (no specification provided)

Source of Sample: B-2 Depth: 10-12'
 Sample Number: ST-2

Date: 10-13-15

Terracon, Inc.

Cincinnati, Ohio


Client: AEP
 Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Project No: N4155126

Exhibit

Tested By: DR Checked By: GS

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	GRAY LEAN CLAY	30	21	9	98.1	93.0	CL

Project No. N4155126 **Client:** AEP
Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION



● Source of Sample: B-2 **Depth:** 10-12' **Sample Number:** ST-2

Remarks:
 ● Initial MC - 27.2%

Terracon, Inc.

Cincinnati, Ohio

Exhibit
 Exhibit B-29



Sample No.		1
Initial	Water Content, %	27.2
	Dry Density, pcf	94.9
	Saturation, %	94.7
	Void Ratio	0.7768
	Diameter, in.	2.860
	Height, in.	6.020
At Test	Water Content, %	27.2
	Dry Density, pcf	94.9
	Saturation, %	94.7
	Void Ratio	0.7768
	Diameter, in.	2.860
	Height, in.	6.020
Strain rate, in./min.		0.060
Back Pressure, psi		0.000
Cell Pressure, psi		0.750
Fail. Stress, psi		7.691
Ult. Stress, psi		
σ_1 Failure, psi		8.441
σ_3 Failure, psi		0.750

Type of Test:
Unconsolidated Undrained

Sample Type: ST

Description: GRAY LEAN CLAY

LL= 30 PL= 21 PI= 9

Assumed Specific Gravity= 2.70

Remarks:

Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-2 **Depth:** 10-12'

Sample Number: ST-2

Proj. No.: N4155126 **Date Sampled:** 10-13-15

TRIAXIAL SHEAR TEST REPORT






Terracon, Inc.
Cincinnati, Ohio

Exhibit 7356

Tested By: FCE

Checked By: GS

Exhibit B-30



Client: AEP

Project: ROCKPORT PLANT IMPROVEMENT CERTIFICATION

Source of Sample: B-2 Depth: 10-12' Sample Number: ST-2

Project No.: N4155126


Exhibit _____

Terracon, Inc.

Tested By: FCE

Checked By: GS

Document Path: P:\GIS - Projects\AEP\mxd\2016-04\04_XSectionLocation.mxd



- Legend**
- Monitoring Well Cluster
 - USWAG Monitoring Well
 - Water Supply Well
 - Cross Section Lines
 - Property Boundary
 - Bottom Ash

Data Sources
 Date of Photography: May-June 2016
 Source of Photography: U.S. Department of Agriculture, National Agriculture Imagery Program (NAIP)




**CROSS SECTION
 LOCATION MAP
 BOTTOM ASH PONDS
 AEP - ROCKPORT, IN**

PROJECT NUMBER: 7382153161

SCALE	1" = 400'	FIG. 4
DATE	9/14/2017	
DRAWN BY	TMR	
APPROVED BY	ALD	

2456 Fortune Drive, Suite 100
 Lexington, Kentucky 40509
 Phone: (859) 255-3308



0' 400'
 SCALE: 1"=400'
 VERTICAL EXAGGERATION: 20X



amec foster wheeler
 Environment & Infrastructure, Inc.
 2456 Fortune Drive, Suite 100
 Lexington, Kentucky 40509
 Phone: (859) 255-3308


**BOTTOM ASH PONDS
 AEP - ROCKPORT, INDIANA**

CROSS SECTION A - A'

PROJECT NUMBER: 7382-15-3161

SCALE	1" = 400'
DATE	05/20/2016
DRAWN BY	VM / TMR
APPROVED BY	ALD

FIG. 5



0' 400'
 SCALE: 1"=400'
 VERTICAL EXAGGERATION: 20X



amec foster wheeler
 Environment & Infrastructure, Inc.
 2456 Fortune Drive, Suite 100
 Lexington, Kentucky 40509
 Phone: (859) 255-3308


**BOTTOM ASH PONDS
 AEP - ROCKPORT, INDIANA**

CROSS SECTION B - B'

PROJECT NUMBER: 7362-15-3161

SCALE	1" = 400'
DATE	05/20/2016
DRAWN BY	VM / TMR
APPROVED BY	ALD

**FIG.
 6**



LEGEND:

- USCS Low Plasticity Clay
- USCS High Plasticity Clay
- USCS Low Plasticity Silty Clay
- USCS Silt
- USCS Poorly-graded Sand
- USCS Well-graded Sand
- USCS Well-graded Sand with Silt
- USCS Well-graded Gravel
- Well Sorted Sand
- Fill or Reworked Soil
- Surficial Silt and Clay
- Shale
- Shale Bedrock
- Screened Interval
- Water level elevation measured in shallow wells on 17 March 2016

0' 400'
SCALE: 1"=400'
VERTICAL EXAGGERATION: 20X



amec foster wheeler
Environment & Infrastructure, Inc.
2456 Fortune Drive, Suite 100
Lexington, Kentucky 40509
Phone: (859) 255-3308

**BOTTOM ASH PONDS
AEP - ROCKPORT, INDIANA**

CROSS SECTION C - C'

PROJECT NUMBER: 7382-15-3161

SCALE	1" = 400'
DATE	05/20/2016
DRAWN BY	VM / TMR
APPROVED BY	ALD

FIG. 7

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**
 COMPANY **INDIANA MICHIGAN POWER COMPANY**
 PROJECT **ROCKPORT PLANT**
 COORDINATES **N 151,510.2 E 514,204.9**
 GROUND ELEVATION **399.9** SYSTEM **State Plane using NAD27/29**

BORING NO. **MW-1604D** DATE **4/27/16** SHEET **1** OF **6**
 BORING START **1/15/16** BORING FINISH **1/15/16**
 PIEZOMETER TYPE _____ WELL TYPE **OW**
 HGT. RISER ABOVE GROUND **2.59** DIA **2.0**
 DEPTH TO TOP OF WELL SCREEN **115.6** BOTTOM **125.15**
 WELL DEVELOPMENT **YES** BACKFILL _____
 FIELD PARTY **ZLR / REB** RIG **D-120**

Water Level, ft	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
TIME			
DATE			

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO									
1	SS	0.0	1.5	17-29-28	.6					Surface gravel		
2	SS	1.5	3.0	8-10-10	1.0				CL	Lean silty clay, dark yellowish brown 10YR 4/2, dry to moist, v. stiff @ 3' trace black oxide nodules, some l. brown silt seams, hard		
3	SS	3.0	4.5	10-19-30	1.0							
4	SS	4.5	6.0	5-15-15	1.2		5					
5	SS	5.0	6.5	5-5-9	1.1							
6	SS	7.5	9.0	7-6-9	1.2				CL	Lean silty clay, dark yellowish brown 10YR 4/2, moist, stiff, some medium dark gray N4 silt seams @ 9' wood (~1")		
7	SS	9.0	10.5	6-5-9	1.2		10					
8	SS	10.0	11.5	4-2-3	1.3							
9	SS	12.0	13.5	5-5-7	1.5				CH	Fat clay, olive gray 5Y 4/1, moist, firm, trace black oxide nodules @ 12' stiff @ 13' some moderate yellowish brown 10YR 5/4 silty clay mottled		
10	SS	13.5	15.0	4-5-9	1.5				CH	Fat clay, medium dark gray N4, and silty lean clay, dark yellowish brown 10YR 4/2, mottled, moist, stiff @ 15' tools sunk / 1" spoon driven / material same, pp same, N value inferred @ 15.5' trace black oxide		
11	SS	15.0	16.5	5-6-5	1.0		15					
12	SS	16.5	18.0	2-3-5	1.5							
13	SS	18.0	19.5	3-4-7	1.5				CL ML	Lean silty clay, moderate yellowish brown 10YR 5/4, moist, firm to stiff, w/medium dark gray N4 fat clay seams (~15%)		
14	SS	19.5	21.0	2-3-4	1.4							

TYPE OF CASING USED

	NQ-2 ROCK CORE
	6" x 3.25 HSA
	9" x 6.25 HSA
	HW CASING ADVANCER 4"
	NW CASING 3"
	SW CASING 6"
	AIR HAMMER 8"

Continued Next Page

PIEZOMETER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE SLOTTED SCREEN, G = GEONOR, P = PNEUMATIC
 WELL TYPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON

RECORDER **AMEC FOSTER WHEELER**

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1604D** DATE **4/27/16** SHEET **2** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **1/15/16** BORING FINISH **1/15/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
15	SS	21.0	22.5	4-4-4	1.5				ML	Clayey silt, moderate yellowish brown 10YR 5/4, moist, loose		
16	SS	22.5	24.0	2-3-3	1.5				SP	Fine grained sand, moderate yellowish brown 10YR 5/4, moist, loose, poorly graded @ 22.2' ~3" seam clayey silt, moderate yellowish brown 10YR 5/4, moist, loose @ 23.8' ~ 2" silt seam		
17	SS	24.0	25.5	1-1-2	1.0		25		ML	Sandy silt to silty sand, light brown 5YR 5/6, moist, v. loose		
18	SS	25.5	27.0	1-1-2	1.0							
19	SS	27.0	28.5	1-1-5	.83							
20	SS	28.5	30.0	1-5-7	.6				SP	Fine sand, dark yellowish orange 10YR 6/6, moist, loose, poorly graded @ 29' transitioning to moderate yellowish brown 10YR 5/4, moist, sample SS20 spilled		
21	SS	30.0	31.5	5-11-12	.8		30		SP	Fine sand, moderate yellowish brown 10YR 5/4, moist, med. dense, poorly graded @ 31.5' moist, dark yellowish brown 10YR 4/2, loose @ 33' v. loose, water in spoon, wet		
22	SS	31.5	33.0	2-4-3	1.1							
23	SS	33.0	34.5	4-1-3	.8							
24	SS	34.5	36.0	4-3-5	.7		35					
25	SS	36.0	37.5	10-6-9	1.5				SW	Coarse grained sand, dark yellowish brown 10YR 4/2, wet loose, well rounded fine gravel, well graded @ 36.5' v. stiff lean clay moderate yellowish brown 10YR 5/4 seam, higher N value likely due to clay, ~30% clay over last 12" longitudinally @ 38' clay seam @ 40' sand sample mostly washed out clay seam (lean clay, moderate yellowish brown 10YR 5/4, wet, v. stiff) ~50%		
26	SS	37.5	39.0	12-10-12	1.5							
27	SS	39.0	40.5	14-14-16	.6		40					
28	SS	40.5	42.0	5-12-19	1.5				SP	Medium grained sand, moderate yellowish brown 10YR 5/4, wet, dense, poorly graded, well rounded fine gravel @ 42' med dense, well rounded fine gravel		
29	SS	42.0	43.5	8-10-10	1.5							
30	SS	43.5	45.0	14-16-11	1.5							
31	SS	45.0	46.5	3-9-12	1.5		45		SW	Coarse grained sand, moderate yellowish brown 10YR 5/4, wet med. dense, w/well rounded fine gravel (to 1/2"), well graded		

Continued Next Page

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1604D** DATE **4/27/16** SHEET **3** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **1/15/16** BORING FINISH **1/15/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
32	SS	46.5	48.0	17-8-9	1.1							
33	SS	48.0	49.5	5-10-11	1.5							
34	SS	49.5	51.0	10-11-12	1.5		50		SP	Fine to med. grained sand, moderate yellowish brown 10YR 5/4, wet, med. dense, poorly graded, w/well rounded fine gravel @ 49.5' trace well rounded fine gravel @ 51' dense, moist @ 55.5' med. dense, transitioning to med. grain @ 57' w/well rounded fine to coarse gravel and rounded sandstone to ~1" @ 60' fully med. grained @ 61.5' w/well rounded fine to coarse gravel and rounded sandstone to 2" @ 63' fine to med. grain, well rounded fine gravel @ 67.5' trace black silt @ 70.5' mostly fine grained, no stone, wet @ 74.8' 1" seam, potential coal or slate, black N1, wet, coarse black N1 silt @ 75' back to fine to med. grain, trace small gravel (~1/4")		
35	SS	51.0	52.5	8-17-18	1.2							
36	SS	52.5	54.0	15-16-16	1.3							
37	SS	54.0	55.5	5-11-19	1.5							
38	SS	55.5	57.0	8-10-12	1.0		55					
39	SS	57.0	58.5	8-12-13	1.1							
40	SS	58.5	60.0	13-9-9	1.1							
41	SS	60.0	61.5	12-9-14	.8		60					
42	SS	61.5	63.0	10-10-11	.8							
43	SS	63.0	64.5	6-10-11	.8							
44	SS	64.5	66.0	7-9-13	1.0		65					
45	SS	66.0	67.5	7-10-16	.7							
46	SS	67.5	69.0	9-10-13	.8							
47	SS	69.0	70.5	8-12-14	.8							
48	SS	70.5	72.0	9-9-12	1.0		70					

AEP RK BAP CCR COMPLIANCE.GPJ_AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1604D** DATE **4/27/16** SHEET **4** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **1/15/16** BORING FINISH **1/15/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
49	SS	72.0	73.5	7-10-13	1.0							
50	SS	73.5	75.0	6-10-20	1.3							
51	SS	75.0	76.5	11-13-17	1.2		75					
52	SS	76.5	78.0	8-29-47	.8							
53	SS	78.0	79.5	16-23-19	1.0				SP	Coarse sand with gravel (~50%) to 15", moderate yellowish brown 10YR 5/4, moist, v. dense, well graded @ 78' fine gravel, dense		
54	SS	79.5	81.0	10-13-19	1.5		80					
55	SS	81.0	82.5	7-13-18	1.0				SP	Fine grained sand, moderate yellowish brown 10YR 5/4 to dark yellowish brown 10YR 4/2, moist, dense, trace fine gravel, poorly graded @ 81' moist to wet, no gravel @ 82.5' med. dense, trace gravel @ 84' dense, no gravel @ 85.5' med. dense		
56	SS	82.5	84.0	6-12-17	.9							
57	SS	84.0	85.5	10-16-20	.8		85					
58	SS	85.5	87.0	11-11-17	1.2							
59	SS	87.0	88.5	12-15-13	1.3				CL ML	Lean silty clay, dark yellowish brown 10YR 4/2 to medium dark gray N4, moist to wet, v. stiff, w/sand @ 87.2' fine grained sand, moist med. dense, poorly graded		
60	SS	88.5	90.0	11-8-10	1.3				CL ML	Lean silty clay, dark yellowish brown 10YR 4/2 to medium dark gray N4, moist to wet, v. stiff, w/sand		
61	SS	90.0	91.5	7-6-14	1.2		90		SP	Fine grained sand, dark yellowish brown 10YR 4/2, wet, med. dense, poorly graded		
62	SS	91.5	93.0	6-12-9	1.5				CL ML	Lean silty clay, dark yellowish brown 10YR 4/2, moist to wet, v. stiff, w/sand @ 92.3' 5" sand seam (prev material) @ 93.5' 4" sand seam (prev material)		
63	SS	93.0	94.5	7-6-16	1.3							
64	SS	94.5	96.0	9-11-12	1.5		95					
65	SS	96.0	97.5	9-8-9	.8				SP	Fine grained sand, dark yellowish brown 10YR 4/2, wet, med. dense, poorly graded, trace pea gravel		
66	SS	97.5	99.0	13-13-14	.8				SW	Coarse sand and gravel, dark yellowish brown 10YR 4/2, moist to wet, med. dense, well graded, gravel to 1.5"		

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1604D** DATE **4/27/16** SHEET **5** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **1/15/16** BORING FINISH **1/15/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
67	SS	99.0	100.5	13-21-15	1.0		100					
68	SS	100.5	102.0	5-8-12	1.3			SP	Shale, medium dark gray N4, moist, v. stiff to hard, dark yellowish brown 10YR 4/2 w/sand			
69	SS	102.0	103.5	9-13-13	1.1				Fine grained sand, dark yellowish brown 10YR 4/2, v. moist med. dense			
70	SS	103.5	105.0	5-3-8	1.4			SC	Clayey sand, fine grained, dark yellowish brown 10YR 4/2, wet, loose			
71	SS	105.0	106.5	7-11-17	1.4		105					
72	SS	106.5	108.0	10-15-15	1.3			SP	Very fine grain sand, moderate yellowish brown 10YR 5/4, moist to wet, med. dense, poorly graded			
73	SS	108.0	109.5	6-11-18	1.3			SP	Fine to med. grained sand, moderate yellowish brown 10YR 5/4 to medium dark gray N4, moist to wet, med. dense, poorly graded			
74	SS	109.5	111.0	9-17-18	1.2		110		@ 100' dense @ 111' trace rock to 1.5" @ 112.5' no stone @ 114' med. dense @ 115.5' loose, moist to wet @ 117' med. dense @ 118.5' d. grey, w/black silt @ 120' trace gravel to 1/4", dense @ 121.5' med. dense @ 123' wet, dense			
75	SS	111.0	112.5	8-17-24	1.2							
76	SS	112.5	114.0	14-23-23	1.3							
77	SS	114.0	115.5	6-7-10	1.3							
78	SS	115.5	117.0	5-5-5	1.3		115					
79	SS	117.0	118.5	5-5-6	1.4							
80	SS	118.5	120.0	6-9-15	1.3							
81	SS	120.0	121.5	8-15-20	1.5		120					
82	SS	121.5	123.0	8-10-17	1.5							
83	SS	123.0	124.5	7-12-38	1.5							

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING





JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1604D** DATE **4/27/16** SHEET **6** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **1/15/16** BORING FINISH **1/15/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
84	SS	124.5	126.0	10-13-35	1.4		125			Coarse sand, medium dark gray N4, moist to wet, dense, with gravel moist to wet graded @ 125.3' 2" coal seam (black, dry, coarse) Shale, medium dark gray N4, dry, hard TOR @ 125.8' Spoon refusal @ 126.6' BT @ 126.6'		
85	SS	126.0	127.5	37-50/2	.5							

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**
 COMPANY **INDIANA MICHIGAN POWER COMPANY**
 PROJECT **ROCKPORT PLANT**
 COORDINATES **N 151,478.9 E 513,537.1**
 GROUND ELEVATION **400.4** SYSTEM **State Plane using NAD27/29**

BORING NO. **MW-1605D** DATE **4/27/16** SHEET **1** OF **6**
 BORING START **2/3/16** BORING FINISH **2/3/16**
 PIEZOMETER TYPE _____ WELL TYPE **OW**
 HGT. RISER ABOVE GROUND **3.36** DIA **2.0**
 DEPTH TO TOP OF WELL SCREEN **114.6** BOTTOM **124.22**
 WELL DEVELOPMENT **YES** BACKFILL _____
 FIELD PARTY **ZLR / REB** RIG **D-50**

Water Level, ft	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TIME			
DATE			

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO									
1	SS	0.0	1.5	20-13-10	1.25				CL	Gravel = 6 inches		
2	SS	1.5	3.0	5-15-18	1.25				CL	Silty clay, moderate yellowish brown 10R 5/4 and med l. grey N6 mottled, moist, v. stiff @ 1.5' hard @ 3' v. stiff		
3	SS	3.0	4.5	7-9-15	1.41							
4	SS	4.5	6.0	11-12-14	1.5		5					
5	SS	6.0	7.5	4-8-11	1.41							
6	SS	7.5	9.0	3-6-11	1.33				ML	Clayey silt, medium grey N5, moist, med. dense, w/mod. yellowish brown 10R 5/4 silty clay mottled		
7	SS	9.0	10.5	3-4-7	1.41		10		CL	Silty clay, mod. yellowish brown 10R 5/4, moist, stiff, w/mod. grey N5 clayey silt mottled		
8	SS	10.5	12.0	3-4-6	1.5							
9	SS	12.0	13.5	2-2-4	1.5				CH	Fat to lean clay, med. l. grey N6, moist, firm		
10	SS	13.5	15.0	2-2-5	1.41							
11	SS	15.0	16.5	2-4-5	1.5		15		CL ML	Silty clay, mod. reddish brown 10R 4/6 w/mod. l. grey N6 fat clay heavily mottled, moist, firm @ 15' stiff @ 15.5' l" shale fragment, angular @ 18' very silty @ 20' trace to some pale yellowish brown 10YR 6/2 silt		
12	SS	16.5	18.0	3-5-9	1.5							
13	SS	18.0	19.5	3-6-8	1.41							
14	SS	19.5	21.0	3-5-7	1.41							

TYPE OF CASING USED

	NQ-2 ROCK CORE
	6" x 3.25 HSA
	9" x 6.25 HSA
	HW CASING ADVANCER 4"
	NW CASING 3"
	SW CASING 6"
	AIR HAMMER 8"

Continued Next Page

PIEZOMETER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE SLOTTED SCREEN, G = GEONOR, P = PNEUMATIC
 WELL TYPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON

RECORDER **AMEC FOSTER WHEELER**

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1605D** DATE **4/27/16** SHEET **2** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **2/3/16** BORING FINISH **2/3/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
15	SS	21.0	22.5	3-4-7	1.5				ML	Clayey silt, pale yellowish brown 10YR 6/2, moist, med. dense, w/silty clay (prev. material), trace sand		
16	SS	22.5	24.0	4-4-5	1.5				SP	Poorly graded sand, v. fine to fine grained, l. brown 5YR 5/6, moist, loose @ 23.2' 2" clayey silt seam (prev. material)		
17	SS	24.0	25.5	1-1-3	1.5		25		ML	Clayey silt, pale yellowish brown 10YR 6/2, moist to wet, v. loose @ 25' 2" l. brown sand seam (prev. material) @ 26' 2" l. brown sand seam @ 26.4' 15" l. brown sand seam @ 26.8' 1" l. brown sand seam @ 27' loose @ 28' 2" l. brown sand seam		
18	SS	25.5	27.0	1-1-1	1.5				SP	Poorly graded sand, fine grained, l. brown 5YR 5/6, moist, med. dense @ 30' d. yellowish orange 10YR 6/6 @ 31' 3" clayey silt seam (prev. material) @ 32.3' trace fine gravel and black silt @ 32.5' no fine gravel or silt @ 33' moist, loose @ 34.1' 2" clayey silt seam (prev. material) @ 34.5' moist to wet, water in spoon @ 34.9' 2.5' clayey silt seam (prev. material)		
19	SS	27.0	28.5	2-1-4	1.5							
20	SS	28.5	30.0	5-6-7	1.33							
21	SS	30.0	31.5	3-5-7	1.25		30					
22	SS	31.5	33.0	5-7-8	1.5							
23	SS	33.0	34.5	3-3-6	1.41							
24	SS	34.5	36.0	2-4-5	1.5		35					
25	SS	36.0	37.5	2-4-6	1.33							
26	SS	37.5	39.0	4-3-8	1.5				SW	Well graded sand, fine grained, l. brown 5YR 5/6, moist to wet, med. dense, w/fine gravel		
27	SS	39.0	40.5	3-3-5	1.5		40		SP	Well graded sand, coarse grained, grayish black N2, moist to wet, med. dense, trace fine gravel		
28	SS	40.5	42.0	11-8-10	1.25				SW	Poorly graded sand, v. fine grained, l. brown 5YR 5/6, moist to wet, med. dense		
29	SS	42.0	43.5	4-5-11	1.5				SP	Well graded sand, fine to med. grained, moderate yellowish brown 10YR 5/4, moist to wet, loose @ 40.5' med. dense @ 41' 1.5" shale seam w/clay		
30	SS	43.5	45.0	8-9-9	1.16				SW	Poorly graded sand, v. fine to fine grained, mod. yellowish brown 10YR 5/4, moist to wet, med. dense		
31	SS	45.0	46.5	6-9-14	1.5		45		SP	Well graded sand, med. grained, mod. reddish brown 10R 4/6, moist to wet, med. dense @ 44' med. to coarse grained		
										Poorly graded sand, fine grained, mod. yellowish		

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1605D** DATE **4/27/16** SHEET **3** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **2/3/16** BORING FINISH **2/3/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
32	SS	46.5	48.0	6-8-11	1.5		50		SW	brown 10YR 5/4, moist to wet, mod. dense, some fine gravel		
33	SS	48.0	49.5	6-10-14	1.5				SP	Well graded sand, med. to coarse grained, mod. reddish brown 10R 4/6, moist to wet, mod. dense, trace fine gravel		
34	SS	49.5	51.0	8-12-18	1.33					Poorly graded sand, fine grained, mod. yellowish brown 10YR 5/4, moist to wet, mod. dense, trace fine gravel @ 48' w/fine gravel, trace coarse gravel @ 49.5' no coarse gravel		
35	SS	51.0	52.5	8-11-18	1.41							
36	SS	52.5	54.0	8-9-13	.91		55		SW	Well graded sand, med. to coarse grained, mod. reddish brown 10R 4/6, moist to wet, mod. dense, trace fine gravel		
37	SS	54.0	55.5	11-20-26	1.25				SP	Poorly graded sand, fine grained, mod. yellowish brown 10YR 5/4, moist to wet, mod. dense, trace fine gravel @ 54' no fine gravel, dense @ 57' wet, mod. dense @ 60' dense @ 63' mod. dense		
38	SS	55.5	57.0	10-15-16	1.5							
39	SS	57.0	58.5	6-12-16	1.33							
40	SS	58.5	60.0	7-10-18	1.33		60					
41	SS	60.0	61.5	8-9-12	1.33							
42	SS	61.5	63.0	10-13-19	1.25							
43	SS	63.0	64.5	9-11-18	1.33							
44	SS	64.5	66.0	9-11-15	1.08		65		SW	Well graded sand, med. to coarse grained, mod. yellowish brown 10YR 5/4, moist to wet, mod. dense, trace black silt		
45	SS	66.0	67.5	7-8-13	1.41				SP	Poorly graded sand, fine grained, mod. yellowish brown 10YR 5/4, moist to wet, mod. dense @ 68.5' trace fine gravel, trace coal fragments @ 70' no fine gravel, no coal fragments @ 70.9' trace fine gravel @ 71.6' no fine gravel, wet		
46	SS	67.5	69.0	5-5-8	1.5							
47	SS	69.0	70.5	6-8-12	1.5							
48	SS	70.5	72.0	0-12-16	1.5		70					

AEP RK BAP CCR COMPLIANCE.GPJ_AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1605D** DATE **4/27/16** SHEET **4** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **2/3/16** BORING FINISH **2/3/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES	
		FROM	TO			%							
49	SS	72.0	73.5	8-8-10	1.25		75		SW	Well graded sand, fine grained d. yellowish brown 10YR 4/2, moist to wet, mod. dense, trace fine gravel @ 73.5' w/fine gravel, trace coarse gravel			
50	SS	73.5	75.0	9-12-17	1.41				SW	Well graded sand, coarse grained, brownish grey 5YR 4/1, moist to wet, mod. dense, w/fine gravel, trace coarse gravel			
51	SS	75.0	76.5	8-7-9	1.5				SP	Poorly graded sand, fine grained, pale yellowish brown 10YR 6/2, wet, dense, trace fine gravel @ 78' mod. dense @ 81' v. fine to fine grained @ 82.5' no fine gravel @ 84' dense @ 85' 2" shale fragment @ 85.2' v. fine grained @ 85.5' 3.5" shale fragment @ 87' fine grained, d. yellowish brown 10YR 4/2 @ 88.5' v. fine grained, mod. dense			
52	SS	76.5	78.0	10-15-25	1.5		80						
53	SS	78.0	79.5	7-13-12	1.33								
54	SS	79.5	81.0	5-7-12	1.5								
55	SS	81.0	82.5	6-12-13	1.5								
56	SS	82.5	84.0	8-10-16	1.41		85						
57	SS	84.0	85.5	10-21-22	1.41								
58	SS	85.5	87.0	14-21-14	.5								
59	SS	87.0	88.5	6-13-25	1.41		90						
60	SS	88.5	90.0	8-9-9	1.16				ML	Clayey silt, med. l. grey N6, moist to wet, mod. dense			
61	SS	90.0	91.5	15-24-7	1.41				SP	Poorly graded sand, fine grained, d. yellowish brown 10YR 4/2, moist, dense			
62	SS	91.5	93.0	7-21-28	1.5		95		ML	Clayey silt, med. l. grey N6, moist to wet, dense			
63	SS	93.0	94.5	14-18-21	1.5				SW	Well graded sand, coarse grained, med. grey N5, w/fine gravel, some coarse gravel			
64	SS	94.5	96.0	12-17-25	1.5				ML	Clayey silt, med. l. grey N6, moist to wet, dense			
65	SS	96.0	97.5	20-21-19	1.33		95		SW	Well graded sand, fine grained, med. grey N5, moist to wet, dense, w/fine gravel			
66	SS	97.5	99.0	13-11-18	1.41				ML	Clayey silt, med. l. grey N6, moist to wet, dense			
									SW	Well graded sand, coarse grained, med. grey N5, moist to wet, dense, w/fine gravel @ 98.7' coal fragments			

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1605D** DATE **4/27/16** SHEET **5** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **2/3/16** BORING FINISH **2/3/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
67	SS	99.0	100.5	15-22-28	1.5		100		SP	Poorly graded sand, v. fine to fine grained, pale yellowish brown 10YR 6/2, moist to wet, dense, w/fine gravel @ 100.5' no fine gravel, mod. dense @ 102' v. fine, dense @ 105' mod. dense @ 106' trace coal fragments @ 106.3' no coal fragments @ 109.5' moist @ 111' v. moist to wet @ 112.5' moist to wet, dense @ 113' trace fine gravel, trace coarse gravel @ 113.5' no fine gravel, no coarse gravel		
68	SS	100.5	102.0	8-8-9	1.5							
69	SS	102.0	103.5	10-16-18	1.5							
70	SS	103.5	105.0	9-13-18	1.41							
71	SS	105.0	106.5	8-12-16	1.5		105					
72	SS	106.5	108.0	6-9-13	1.5							
73	SS	108.0	109.5	7-8-12	1.25							
74	SS	109.5	111.0	6-8-10	1.41		110					
75	SS	111.0	112.5	5-10-12	1.25							
76	SS	112.5	114.0	6-11-27	1.33							
77	SS	114.0	115.5	13-21-13	1.25		115	SW	Well graded sand, med. to coarse grained, med. grey N5, moist to wet, dense, w/fine gravel, some coarse gavel @ 115.5' coarse grained, mod. dense, trace coarse gravel @ 118.5' v. dense			
78	SS	115.5	117.0	7-7-9	1.33							
79	SS	117.0	118.5	9-9-8	1.16							
80	SS	118.5	120.0	12-36-22	1.5							
81	SS	120.0	121.5	10-11-19	1.41		120	SP	Poorly graded sand, v. fine grained, med. l. grey N6, moist to wet, v. dense @ 120' med. dense, sl. moist @ 122' fine grained, w/fine gravel, dense @ 124.5' trace coarse gravel			
82	SS	121.5	123.0	12-20-29	1.5							
83	SS	123.0	124.5	14-16-19	1.5							

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1605D**

DATE **4/27/16**

SHEET **6** OF **6**

PROJECT **ROCKPORT PLANT**

BORING START **2/3/16**

BORING FINISH **2/3/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
84	SS	124.5	126.0	18-12-25	1.5		125					
85	SS	126.0	127.5	17-28-50/5	1.5				ML	Clayey silt, l. grey N7, moist, hard, non-durable shale @ 126' flaky, dry to moist Spoon refusal @ 127.4' Auger refusal @127.5' (shale)		
86	SS	127.5	129.0	27-50/2	.66							

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**
 COMPANY **INDIANA MICHIGAN POWER COMPANY**
 PROJECT **ROCKPORT PLANT**
 COORDINATES **N 151,502.1 E 512,881.5**
 GROUND ELEVATION **397.8** SYSTEM **State Plane using NAD27/29**

BORING NO. **MW-1606D** DATE **4/27/16** SHEET **1** OF **5**
 BORING START **2/12/16** BORING FINISH **2/12/16**
 PIEZOMETER TYPE _____ WELL TYPE **OW**
 HGT. RISER ABOVE GROUND **2.91** DIA **2.0**
 DEPTH TO TOP OF WELL SCREEN **100.2** BOTTOM **109.82**
 WELL DEVELOPMENT **YES** BACKFILL _____
 FIELD PARTY **ZLR / REB** RIG **D-120**

Water Level, ft	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TIME			
DATE			

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO									
1	SS	0.0	1.5	3-5-9	1.5				CL	Crushed stone gravel (limestone)		
2	SS	1.5	3.0	4-7-9	1.5					Lean clay, moderate yellowish brown 10YR 5/4, moist, trace fine grained sand, stiff @ 1.5' as above, trace coarse grain sand and black decomposed organic staining @ 3' trace fine gravel		
3	SS	3.0	4.5	3-4-6	1.3							
4	SS	4.5	6.0	1-2-8	1.3		5					
5	SS	6.0	7.5	5-9-10	1.5				CL	Lean clay, pale yellow brown 10YR 6/2, moist, some light brown oxide staining @ 6.0' yellow brown and brown 10YR 5/4 @ 7.5' pale yellow brown 10YR 6/2, trace fine roots, trace fine grained sand		
6	SS	7.5	9.0	3-6-9	1.5				CL	Lean clay w/sand, dark yellow brown 10YR 4/2, moist, little fine grained sand		
7	SS	9.0	10.5	2-4-5	1.5		10		CL	Lean clay, light bluish gray 5B 7/1, moist, some brown oxide staining, trace coarse grained sand @ 12.5' as above, becomes moderate brown in color 5YR 4/4 @ 13.5' moderate yellow brown 10YR 5/4 and pale yellow brown 10YR 6/2) mottled @ 13.5' - 15' trace fine grained sand, trace fine gravel @ 19.5' mostly 10YR 6/2 in color		
8	SS	10.5	12.0	3-4-6	1.5							
9	SS	12.0	13.5	3-5-9	1.5							
10	SS	13.5	15.0	4-5-7	1.5							
11	SS	15.0	16.5	3-5-6	1.5		15					
12	SS	16.5	18.0	3-4-6	1.5							
13	SS	18.0	19.5	2-5-7	1.5							
14	SS	19.5	21.0	3-3-6	1.5							

TYPE OF CASING USED

_____	NQ-2 ROCK CORE
_____	6" x 3.25 HSA
_____	9" x 6.25 HSA
_____	HW CASING ADVANCER 4"
_____	NW CASING 3"
_____	SW CASING 6"
_____	AIR HAMMER 8"

Continued Next Page

PIEZOMETER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE SLOTTED SCREEN, G = GEONOR, P = PNEUMATIC
 WELL TYPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON

RECORDER **AMEC FOSTER WHEELER**

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1606D** DATE **4/27/16** SHEET **2** OF **5**

PROJECT **ROCKPORT PLANT**

BORING START **2/12/16** BORING FINISH **2/12/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
15	SS	21.0	22.5	3-4-5	1.5							
16	SS	22.5	24.0	2-4-6	1.5			CL ML		Silty clay, pale yellow brown 10YR 6/2, moist, trace to little fine grained sand		
17	SS	24.0	25.5	1-2-5	1.2			SP SM		Poorly graded sand w/silt, pale yellow brown 10YR 6/2, moist, fine to medium grained sand @ 24.9' 3" silt layer		
18	SS	25.5	27.0	2-4-6	1.5		25					
19	SS	27.0	28.5	1-5-9	1.3			CL		Lean clay, moderate yellowish brown 10YR 5/4, moist, few sandy layers <1" thick @ 28.3' SP-SM layer (~3" thick)		
20	SS	28.5	30.0	4-4-5	1.3			SP SM		Poorly graded sand w/silt, dark yellowish orange 10YR 6/6, wet, fine to medium grained sand, little coarse grained sand @ 31.5' trace fine gravel @ 34.5' trace fine gravel		
21	SS	30.0	31.5	5-7-8	1.5		30					
22	SS	31.5	33.0	3-3-4	1.1							
23	SS	33.0	34.5	1-2-5	0							
24	SS	34.5	36.0	3-4-8	.8		35					
25	SS	36.0	37.5	3-5-7	1.0							
26	SS	37.5	39.0	5-6-7	.9			SP		Poorly graded sand, dark yellowish orange 10YR 6/6, wet, fine to medium grained sand, trace to little coarse grained sand @ 37.5' trace gravel		
27	SS	39.0	40.5	4-7-20	1.2			SP SM		Poorly graded sand w/silt, dark yellowish orange 10YR 6/6, wet, fine to medium grained sand, trace coarse grained sand		
28	SS	40.5	42.0	7-7-8	1.1		40	SC		Clayey sand, moderate brown 5YR 3/4, wet, fine to medium grained sand		
29	SS	42.0	43.5	4-6-10	1.0			SP		Poorly graded sand, dark yellowish orange 10YR 6/6, wet, fine to medium grained sand, trace coarse grained sand & fine gravel @ 42.0' - 43.5' increase in coarse grained sand @ 45.2' - 45.5' color change to moderate brown 5YR 4/4 @ 46.5' increase in coarse grained sand, trace wood fragments (tree bark) @ 48' color change to pale yellowish brown 10YR		
30	SS	43.5	45.0	4-5-7	1.0							
31	SS	45.0	46.5	4-6-10	1.2		45					

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1606D** DATE **4/27/16** SHEET **3** OF **5**

PROJECT **ROCKPORT PLANT**

BORING START **2/12/16** BORING FINISH **2/12/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
32	SS	46.5	48.0	8-9-11	1.1					6/2, few black decomposed organic layers		
33	SS	48.0	49.5	6-10-13	1.1							
34	SS	49.5	51.0	18-13-13	.9		50		SW SM	Well graded sand w/silt & gravel, wet, pale yellowish brown 10YR 6/2, fine to coarse grained sand, little to some fine gravel, trace coarse gravel		
35	SS	51.0	52.5	7-14-16	1.1				SP SM	Poorly graded sand w/silt, moderate yellowish brown 10YR 5/4, wet, fine to medium grained sand, trace coarse grained sand, few layers of decomposed organics (from 51' - 52.5') @ 54' trace coarse gravel, fines between 5 - 10% @ 55.5' trace fine gravel		
36	SS	52.5	54.0	7-9-15	1.0							
37	SS	54.0	55.5	10-10-14	1.2		55					
38	SS	55.5	57.0	8-10-13	1.2							
39	SS	57.0	58.5	7-9-9	1.3				SW	Well graded sand, med. to coarse grained, dark yellowish brown 10YR 4/2, wet, med. dense, trace fine gravel @ 59' trace coarse gravel		
40	SS	58.5	60.0	4-5-9	1.2		60		SP	Poorly graded sand, fine grained, dusky yellowish brown 10YR 2/2, wet, med. dense, w/fine gravel @ 60.5' 2" shale fragment @ 61.5' dark yellowish brown 10YR 4/2, dense @ 61.8' 2" shale fragment @ 62' some lean clay, pale yellowish brown (prev. material) @ 62.5' no clay, trace fine gravel @ 63' no fine gravel @ 64.5' med. dense @ 65.8' 15" coarse sand seam (prev. material) @ 66' dense @ 67.2' 3" shale seam, med. l. grey N6 @ 67.7' med. grained		
41	SS	60.0	61.5	6-6-9	1.5							
42	SS	61.5	63.0	6-13-21	1.5							
43	SS	63.0	64.5	10-17-31	1.3							
44	SS	64.5	66.0	13-13-17	1.4		65					
45	SS	66.0	67.5	6-14-18	1.5							
46	SS	67.5	69.0	9-14-17	1.5							
47	SS	69.0	70.5	10-20-20	1.1				SP	Poorly graded sand, fine gravel, pale yellowish brown 10YR 6.2, wet, dense @ 69' moist to v. moist @ 72' med. dense, fine grained @ 75' dense, d. yellowish brown 10YR 4.2 @ 76.5' med. dense, trace black silt @ 80.6 3" shale plug (responsible for increase in N value (same material)) @ 81.3' 1.5" shale plug, dense		
48	SS	70.5	72.0	10-19-26	1.4		70					

AEP_RK_BAP_CCR_COMPLIANCE.GPJ_AEP_GDT_4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**

BORING NO. **MW-1606D** DATE **4/27/16** SHEET **4** OF **5**

PROJECT **ROCKPORT PLANT**

BORING START **2/12/16** BORING FINISH **2/12/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
49	SS	72.0	73.5	7-10-17	1.3		75			@ 81.5' no recovery, potential cobble blocking during sampling		
50	SS	73.5	75.0	8-9-13	1.2							
51	SS	75.0	76.5	10-16-25	1.4							
52	SS	76.5	78.0	9-10-14	1.4							
53	SS	78.0	79.5	6-9-18	1.5							
54	SS	79.5	81.0	10-17-34	1.5							
55	SS	81.0	82.5	31-19-14	1.3							
56	SS	82.5	84.0	10-16-21	1.5							
57	SS	84.0	85.5	9-19-21	1.5							
58	SS	85.5	87.0	7-15-24	1.3							
59	SS	87.0	88.5	10-13-20	1.2							
60	SS	88.5	90.0	8-14-23	1.4							
61	SS	90.0	91.5	8-13-27	1.3							
62	SS	91.5	93.0	8-7-16	1.5							
63	SS	93.0	94.5	7-9-15	1.5							
64	SS	94.5	96.0	12-12-14	1.5							
65	SS	96.0	97.5	3-5-5	1.5							
66	SS	97.5	99.0	5-5-6	1.4							
							95					

AEP RK BAP CCR COMPLIANCE.GPJ AEP.GDT 4/27/16

Continued Next Page

AMERICAN ELECTRIC POWER SERVICE CORPORATION
AEP CIVIL ENGINEERING LABORATORY
 LOG OF BORING



JOB NUMBER **42393125-01**

COMPANY **INDIANA MICHIGAN POWER COMPANY**


BORING NO. **MW-1606D** DATE **4/27/16** SHEET **5** OF **5**

PROJECT **ROCKPORT PLANT**


BORING START **2/12/16** BORING FINISH **2/12/16**

SAMPLE NUMBER	SAMPLE	SAMPLE DEPTH IN FEET		STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	USCS	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
		FROM	TO			%						
67	SS	99.0	100.5	4-5-7	1.5		100			Poorly graded sand, coarse grained, greyish red 5R 4/2, wet, med. dense to loose, trace fine gravel Poorly graded sand, fine grained, pale yellowish brown 10YR 6/2, wet, loose @ 97.5' med. dense, fine grained		
68	SS	100.5	102.0	7-7-10	1.4				SP	Poorly graded sand, fine to fine grained, dusky red 5R 3/4, wet, med. dense		
69	SS	102.0	103.5	4-4-6	1.5					@ 102' loose, fine grained, moist		
70	SS	103.5	105.0	5-6-10	1.3					@ 103.5' med. dense @ 105' fine grained @ 106.5' dense		
71	SS	105.0	106.5	4-6-9	1.5		105			@ 108' med. dense, trace fine gravel @ 109' no fine gravel @110.6' siltstone fragments to 2.5", moderate brown 5YR 4/4, shiny, angular		
72	SS	106.5	108.0	7-11-20	1.4							
73	SS	108.0	109.5	8-13-15	1.5							
74	SS	109.5	111.0	10-18-11	1.3		110					
75	SS	111.0	112.5	14-50/3				ML	Silt, l. grey N7, moist, med. dense, non-durable shale			
76	SS	112.5	114.0	50/4					@ 111' clayey silt, hard Spoon refusal @ 111.7' Auger refusal @ 112.9 BT @ 112.9'			


Appendix D- Original Design Drawings




SECTION 1-1
RECLAIM, WASTEWATER & BOTTOM ASH PONDS
SCALE 1" = 30'
FOR LOCATIONS SEE DWG NO. 12-30013




SECTION 2-2
NORTH METAL CLEANING WASTE BASIN & E-W BOTTOM ASH PONDS
SCALE 1" = 30'
FOR LOCATIONS SEE DWG NO. 12-30013



DETAIL 8-B
SCALE 1" = 10'
FOR LOCATION SEE DWG NO. 12-30013



SECTION 9-B
SCALE 1" = 10'
FOR LOCATION SEE DWG NO. 12-30013



GENERAL NOTES

- REFERENCE DRAWINGS**
- 12-3003 WASTEWATER & BOTTOM ASH POND AREA, GRADINGS & DRAINAGE
 - 12-30023 SEDIMENTATION BASINS - LOCATION PLAN
 - 12-30024 SEDIMENTATION BASINS - PLANS & DETAILS

DATE	NO.	DESCRIPTION	APP'D.
11/01/77	1	AS PER CIVIL ENGR'S REQUEST, REVISED WEST BOT. ASH POND EL. TO 386.0 WAS 377.0, ADDED NOTE: BOT. EL. 377.0 FOR W.W.22	H/S
09/17/80	2	RELEASED TO FIELD	H/S

REVISIONS

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

INDIANA & MICHIGAN ELECTRIC CO.
ROCKPORT SITE
ROCKPORT, INDIANA

UNIT No. 1 & 2
WASTEWATER & BOTTOM ASH POND AREA - SECTIONS & DETAILS

DR. NO. 12-30018-1

ARCH.	ELEC.	MECH.	P&I	STR.	S.F.

LOCAL: AS NOTED
 DESIGNED BY: J.P. SHIMBLE
 CHECKED BY: J.P. SHIMBLE
 DATE: 7/11/77


APPROVED BY: [Signature]
 DATE: 7/11/77

AMERICAN ELECTRIC POWER SERVICE CORP.


12-3002-21 ON RD

ROAD / DIKE BASE COURSE DATA				
TOTAL ROAD/DIKE WIDTH (A)	1/2 LANE WIDTH (B)	THICKNESS OF WELL-COMPACTED STONE #53 FOR THE LANE (C)	STABILIZED SHOULDER WIDTH (D)	THICKNESS OF WELL-COMPACTED STONE #53 FOR SHOULDER (E)
20'	6'	6"	4'	3"
30'	15'	12"	0'	0"
40'	15'	12"	5'	6"


GENERAL NOTES
FOR CONTINUATION OF 66" CMP - SEC. G-2
SEE PROFILE SH. 12-3002B.




SECTION C-2
SCALE: 1" = 20'




SECTION G-2
SCALE: 1" = 20'




TYPICAL SECTION 2-K
FOR REGRADE & REDRESS OF SLOPES ON BOTTOM ASH, WASTEWATER, RECLAIM & CLEARWATER PONDS
SCALE: 1/4" = 1'-0"




SECTION C-3
SCALE: 1" = 20'




SECTION G-3
SCALE: 1" = 20'




SECTION C-4
SCALE: 1" = 20'




SECTION G-5
SCALE: 1" = 20'




SECTION C-6
SCALE: 1" = 20'




SECTION G-6
SCALE: 1" = 20'




SECTION C-7
SCALE: 1" = 20'



SECTION C-9
SCALE: 1" = 20'



DETAIL 9G
SCALE: 3/8" = 1'-0"



ELEVATION J9

REFERENCE DRAWINGS
12-3003 WASTEWATER & BOTTOM ASH POND AREA GRADING & DRAINAGE
12-3004 AREA SOUTH OF RECLAIM POND - GRADING, DRAINAGE & TRACK LAYOUT

DATE	NO.	DESCRIPTION	APPD.
4/12/19	8	ADDED TYP DET 9G FOR REGRADE & REDRESS OF SLOPES ON BOTTOM ASH, WASTEWATER, RECLAIM & CLEARWATER PONDS.	W/S
2/17/19	7	ADDED SKIMMER SECT G-2 PER R.O.R. ROCK #12-270, R/S. ADDED SECTION G-G.	SF
3/17/19	6	REVISED DESCRIPTION OF STEEL PIPE TO FIBERGLASS DUCT. REVISED PIPE LENGTH DIMS. SEC. C-2, C-3, C-4 & C-6. REVISED PIPE BEND SECTION C-3 & C-9. ADDED LENGTH DIMENSION & REVISED INV. EL. OF 30" STEEL PIPES. REV. LENGTH DIM. OF 66" CMP TO 80". WAS 100".	W/S
4/12/19	4	RELOCATED STRUCT # 6 & #12. REVISED INV. ELEVATIONS AND BASE OF RECLAIM POND. REVISED SECTIONS C-2, C-3, C-4 & C-6. RELOCATED STRUCT # 9 FROM CLEAR WATER POND TO RECLAIM PD & REVISED FLOW.	W/S
4/12/19	3	REVISED SECTION G-2, CHANGED PIPE SIZE 48" TO 36".	W/S
4/12/19	2	ADDED 48" CMP & SLIDE GATES TO SECTIONS C-4 & C-6. RAISED WEST BOTTOM ASH POND EL. TO 385.0 WAS 377.5. RAISED WEST WASTEWATER POND EL. TO 377.5 WAS 375.0. CORRECTED DIMS. ON SECTION G-3 TO 12'-0". ON ADDED HOLD STRAPS WITH TURNBUCKLE TO DETAIL 9G.	W/S
4/12/19	1	ADDED STRUCTURE NO. 12 TO SECTION C-2.	W/S

REVISIONS
NOTE: GRADE ELEVATION HAS BEEN ESTABLISHED AS ELEVATION TO CONVERT TO PLANT DATUM ADD TO ELEVATIONS SHOWN.

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE A.E.P. SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

INDIANA & MICHIGAN ELECTRIC CO.
ROCKPORT SITE
ROCKPORT, INDIANA

UNIT No. 1 & 2
WASTEWATER & BOTTOM ASH POND AREA - SECTIONS & DETAILS

DR. NO. 12-30027-8

ARCH.	ELEC.	MECH.	STR.

SCALE: AS SHOWN
DR. W. SWINGLE
CH. H.B.
SQ. LDR. J.P.
DATE: 3/5/19

AMERICAN ELECTRIC POWER SERVICE CORP.
2 BROADWAY NEW YORK