

INFLOW DESIGN FLOOD CONTROL PLAN PERIODIC 5-YEAR REVIEW

30 TAC 352.821 (40 CFR 257.82)

Bottom Ash Storage Pond

Welsh Power Plant
Pittsburg, Texas

October, 2021

Prepared for: Southwest Electric Power Company – Welsh Power Plant

Pittsburg, Texas

Prepared by: American Electric Power Service Corporation

1 Riverside Plaza

Columbus, OH 43215




DOCUMENT ID: GERS – 21 – 054

INFLOW DESIGN FLOOD CONTROL PLAN
PERIODIC 5-YEAR REVIEW
CFR 257.82
WELSH POWER PLANT
BOTTOM ASH STORAGE POND

PREPARED BY Brett A. Dreger DATE 10/4/2021
Brett A. Dreger, P.E.

REVIEWED BY M.A.L. DATE 10/5/2021
Mohammad A. Ajlouni, P.E.

APPROVED BY Gary F. Zych DATE 10/6/2021
Gary F. Zych, P.E.
Manager – AEP Geotechnical Engineering



I certify to the best of my knowledge, information, and belief that the information contained in this Inflow Design Flood Control Plan meets the requirements of 40 CFR § 257.82

Table of CONTENTS

1.0 OBJECTIVE	1
2.0 DESCRIPTION OF THE CCR UNIT	1
3.0 INFLOW DESIGN FLOOD 257.82(a)(3)	1
4.0 FLOOD CONTROL PLAN 257.82(c)	1

Attachment A: Hydraulic Analysis of Welsh Power Plant Ash Ponds

1.0 OBJECTIVE

This report was prepared by AEP- Geotechnical Engineering Services (GES) section to fulfill requirements of 30 TAC 352.821 (40 CFR 257.82) for the hydrologic and hydraulic evaluation of CCR surface impoundments. This is the first periodic 5-year review of the inflow design flood control plan.

2.0 DESCRIPTION OF THE CCR UNIT

The AEP J. Robert Welsh Plant is located in southern Titus County, approximately 8 miles northeast of Pittsburg, Texas, and approximately two miles northwest of Cason, Texas. The facility operates two surface impoundments for storing CCR materials called the Primary Bottom Ash pond and the Bottom Ash Storage pond. This report addresses the Bottom Ash Storage Pond. The Bottom Ash Storage pond CCR unit is located at the south end of the Plant and approximately 1,000 feet west of the Welsh Reservoir.

In 2000, the 22-acre Bottom Ash Storage Pond was installed south of the landfill. The Bottom Ash Storage Pond receives economizer ash and bottom dredged and sluiced from the primary ash pond.

3.0 INFLOW DESIGN FLOOD 257.82(a)(3)

The facility is classified as a Low Hazard Potential Dam. This classification has not changed since the initial evaluation. The Inflow Design Flood is the 100-year storm event.

4.0 FLOOD CONTROL PLAN 257.82(c)

As of April 11, 2021, the plant has ceased all sluicing operations and all surface water run-on to the Bottom Ash Storage Pond area. The only inflows to the Bottom Ash Storage Pond is direct rainfall within the pond's dikes. The design to safely pass the inflow design flood without overtopping the crest of the dam is based on the normal pool being at maximum normal operating pool and utilizing the principal spillway and emergency spillway to handle the 100-year design storm without overtopping the crest of the dam.

The 2010 Hydraulic Analysis of Welsh Power Plant Ash Ponds report (Attachment A) provides the description of the drainage area, spillway system, flood storage capacity, inflow peak discharge and volume, peak discharge from the facility and maximum pool elevation for the Bottom Ash Storage Pond.

There has not been any changes to spillway system, flood storage capacity or rainfall estimates that would change the results presented in Attachment A. The calculations show that the facility has the capacity to manage the inflow design flood, as well as large flood events.

ATTACHMENT A

Hydraulic Analysis

Of

Welsh Power Plant Ash Ponds



Innovative approaches
Practical results
Outstanding service

Hydraulic Analysis of Welsh Power Plant Ash Ponds

American Electric Power Company

Prepared by:

FREESE AND NICHOLS, INC.
4055 International Plaza, Suite 200
Fort Worth, Texas 76109
817-735-7300

AEP10412

Hydraulic Analysis of Welsh Power Plant Ash Ponds

American Electric Power Company



Freese and Nichols, Inc.
Texas Registered Engineering Firm F-2144

The seal appearing on this document was
authorized by Travis N. Attanasio on
December 29, 2010

Prepared by:
FREESE AND NICHOLS, INC.
4055 International Plaza, Suite 200
Fort Worth, Texas 76109
817-735-7300

AEP10412

TABLE OF CONTENTS

1.0	Introduction	1
2.0	Hydrologic Model Development.....	3
2.1	Basin Delineation & Connectivity.....	3
2.2	Hydrologic Parameters	5
2.3	Elevation-Storage Data	8
2.4	Discharge Rating Curves.....	9
2.5	Frequency Model Results.....	12
2.6	PMF Model Results.....	13
3.0	Summary and Conclusions	15

LIST OF TABLES

Table 1 – Curve Number Calculation Matrix.....	5
Table 2 – Basin Parameters	8
Table 3 – Elevation-Storage Data	9
Table 4 – Discharge Rating Curves	11
Table 5 – Frequency Precipitation Depths	12
Table 6 – 10-Year Storm Results.....	12
Table 7 – 25-Year Storm Results.....	13
Table 8 – 100-Year Storm Results.....	13
Table 9 – HMR-52 Point Rainfall Depths.....	14
Table 10 – 25% PMF Results	14
Table 11 – 50% PMF Results	14
Table 12 – 100% PMF Results	14
Table 13 – Pertinent Dam Information.....	15
Table 14 – Summary of Results.....	15

LIST OF FIGURES

Figure 1 – Location Map	2
Figure 2 – Drainage Basin Map.....	4
Figure 3 – Hydrologic Soil Classifications.....	6
Figure 4 – Land Cover Data.....	7

APPENDICES

Appendix A References


Appendix B Discharge Rating Curve Calculations

Appendix C Pertinent Drawings

1.0 INTRODUCTION

In November of 2010, Freese and Nichols, Inc., (FNI) was retained by American Electric Power (AEP) to perform various hydrologic and hydraulic calculations to determine the hydraulic adequacy of the Primary Ash, Secondary Ash, and Bottom Ash Ponds for the Welsh Power Plant located near Pittsburg, TX. This report summarizes the results of the analysis for the 10-year, 25-year, 100-year, 25% PMF, 50% PMF, and 100% PMF events.

The three Ash Ponds are situated immediately south of the Welsh Power Plant on the west side of Welsh Reservoir. The general location of the power plant and associated reservoirs is shown in Figure 1.



PROJECT NO.	AEP10412
FILE NAME	H:\WR_DESIGN\FIGURES\Figure1_LocationMap.mxd
DATUM & COORDINATE SYSTEM	NAD83 STATE PLANE TEXAS NORTH CENTRAL (FT)
DATE CREATED	DECEMBER 2010
PREPARED BY	JPM



WELSH POWER PLANT ASH PONDS
LOCATION MAP




FIGURE
1

2.0 HYDROLOGIC MODEL DEVELOPMENT

2.1 BASIN DELINEATION & CONNECTIVITY

The hydrologic model for the Welsh Power Plant Ash Ponds was created in HEC-HMS¹ and consisted of seven total drainage basins, as shown in Figure 2. The total drainage area modeled is approximately 0.695 square miles, or 445 acres. Two basins, labeled *Primary* and *Power Plant*, drain directly into the Primary Ash Pond. The Ash Storage Area was divided into two drainage basins – *Ash Storage Area A* and *Ash Storage Area B* – based on a December 2009 survey of the area. A small portion of the Ash Storage Area, along with a small wooded area, drains into the Bottom Ash Pond and is shown as *to Bottom Ash* in Figure 2. Additionally, the area inside the embankment for the Bottom Ash Pond is labeled *Bottom Ash* and drains directly into the reservoir area. Finally, the basin labeled *Secondary* represents the area draining to the Secondary Ash Pond.

Each of the seven basins and three reservoir areas are connected in some way and form an intricate system of connectivity. The only discharges from the Primary Ash Pond flow through a drainage canal to the Secondary Ash Pond. This canal flows from west to east and is controlled by a weir box control structure. Discharges from the Primary Ash Pond emergency spillway also flow into this drainage canal; however, these flows enter the canal downstream of the weir box control structure. Runoff from the Ash Storage Area also enters the Primary Ash Pond via a small sump area with a 24-inch culvert. Rainfall is routed through a small ditch around the perimeter of the Ash Storage Area to this culvert. The principal spillway for the Bottom Ash Pond discharges into a 30-inch pipe which transports the outflows to the Ash Storage Area ditch. These outflows eventually discharge into the Primary Ash Pond. The emergency spillway for the Bottom Ash Pond discharges freely into the area downstream of the Welsh Reservoir emergency spillway. Finally, the combined flows from the drainage canal enter the Secondary Ash Pond, which has both a principal and emergency spillway. All discharges from the Secondary Ash Pond flow into Welsh Reservoir. Spillway capacities are discussed in further detail in Section 2.4.



PROJECT NO.	AEP10412
FILE NAME	H:\WR_DESIGN\FIGURES\Figure2_Basins.mxd
DATUM & COORDINATE SYSTEM	NAD83 STATE PLANE TEXAS NORTH CENTRAL (FT)
DATE CREATED	DECEMBER 2010
PREPARED BY	JPM

FREESE NICHOLS
 4055 International Plaza, Suite 200
 Fort Worth, TX 76109-4895
 817-735-7300

0 500 1,000 2,000 Feet

WELSH POWER PLANT ASH PONDS

DRAINAGE BASIN MAP





FIGURE
2

2.2 HYDROLOGIC PARAMETERS

The HEC-HMS model incorporates the NRCS Curve Number and Unit Hydrograph methods for each basin. In this model, the curve numbers were based on hydrologic soil classifications and land cover. The instantaneous runoff effect of open water surfaces was accounted for in the development of the curve numbers. The soils dataset was obtained from the NRCS Soil Survey Geographic Database² (SSURGO), and land use dataset was obtained from the USGS Seamless Data Warehouse³ in the form of the National Land Cover Dataset (NLCD) for 2001. Spatial information about soil types and land use classifications is presented in Figures 3 and 4, respectively. Table 1 provides the matrix used in determining the curve number for each basin. The curve numbers shown in Table 1 are for Antecedent Moisture Condition (AMC) II. These values were incorporated in the model for the frequency storm events, such as the 100-year storm event. In accordance with TCEQ recommendations, AMC III was applied to the model for PMF events. This represents a worst-case scenario with the ground fully saturated prior to the PMF event.

Table 1 - Curve Number Calculation Matrix

NLCD Classification		Curve Number (AMC II)					
#	Description	A	B	B/C	C	C/D	D
11	Open Water	100	100	100	100	100	100
21	Developed, Open Space	68	79	83	86	88	89
22	Developed, Low Intensity	51	68	74	79	82	84
23	Developed, Medium Intensity	77	85	88	90	91	92
24	Developed, High Intensity	89	92	93	94	95	95
31	Barren Land	77	86	89	91	93	94
41	Deciduous Forest	36	60	67	73	76	79
42	Evergreen Forest	36	60	67	73	76	79
43	Mixed Forest	36	60	67	73	76	79
52	Scrub/Shrub	35	56	63	70	74	77
71	Grassland/Herbaceous	39	61	68	74	77	80
81	Pasture/Hay	39	61	68	74	77	80
82	Cultivated Crops	67	78	82	85	87	89
90	Woody Wetlands	45	66	72	77	80	83



FN PROJECT NO.	AEP10412
FILE NAME	H:\WR_DESIGN\FIGURES\Figure3_Soils.mxd
DATUM & COORDINATE SYSTEM	NAD83 STATE PLANE TEXAS NORTH CENTRAL (FT)
DATE CREATED	DECEMBER 2010
PREPARED BY	JPM

FREESSE NICHOLS
 4055 International Plaza, Suite 200
 Fort Worth, TX 76109-4895
 817-735-7300

0 500 1,000 2,000 Feet
WELSH POWER PLANT ASH PONDS
HYDROLOGIC SOIL CLASSIFICATIONS





FIGURE 3



Basins

LandUse

- 11
- 21
- 22
- 23
- 24
- 31
- 41
- 42
- 43
- 52
- 71
- 81
- 82
- 90


FN PROJECT NO.	AEP10412
FILE NAME	H:\WR_DESIGN\FIGURES\Figure4_LandCover.mxd
DATUM & COORDINATE SYSTEM	NAD83 STATE PLANE TEXAS NORTH CENTRAL (FT)
DATE CREATED	DECEMBER 2010
PREPARED BY	JPM



0 500 1,000 2,000 Feet

WELSH POWER PLANT ASH PONDS

LAND COVER DATA



FIGURE

4

The only input into HEC-HMS for the NRCS Dimensionless Unit Hydrograph is a lag time, which is calculated based on basin conditions, such as hydraulic length and average slope, according to the NRCS TR-55 Method. Table 2 provides a summary of the hydrologic parameters for each basin. Note that AMC II corresponds with the curve numbers used in the frequency model and that AMC III corresponds with the weighted curve numbers used in the PMP model.

Table 2 – Basin Parameters

Basin	Area (mi ²)	Lag Time (min)	Curve Number (AMC II)	Curve Number (AMC III)
Ash Storage A	0.034	5.28	87.1	93.9
Ash Storage B	0.025	7.51	87.1	93.9
Bottom Ash	0.034	4.78	91.0	95.9
Power Plant	0.180	18.77	85.3	93.0
Primary	0.366	36.14	76.0	88.0
Secondary	0.026	2.31	82.7	91.7
to Bottom Ash	0.031	16.51	77.8	89.0

2.3 ELEVATION-STORAGE DATA

Elevation-storage data for each reservoir was obtained from a combination of data sources. The elevation-storage relationship for the Primary Ash Pond was calculated from USGS 10-foot contours for the area and compared to calculations made by AEP. The Secondary Ash Pond used the AEP Calculations for elevation 320.0 ft-msl to elevation 330.0 ft-msl and a combination of USGS 10-foot contours and surveyed 2-foot contours. The Bottom Ash Pond used volume calculations from an April 2010 survey from elevation 346.13 ft-msl to elevation 355.92 ft-msl. The volume was then extrapolated to the top of dam elevation of 360.0 ft-msl by the average-end-area method and the assumption of 3:1 side slopes. These relationships were used in the hydrologic model for routing both frequency storm events and the PMF and are shown in Table 3 below.

Table 3 – Elevation-Storage Data

Primary		Secondary		Bottom Ash	
Elevation (ft-msl)	Storage (acre-ft)	Elevation (ft-msl)	Storage (acre-ft)	Elevation (ft-msl)	Storage (acre-ft)
300	0.00	320	0.00	346.13	0.00
305	22.37	330	36.87	347	0.22
310	54.66	331	41.31	348	1.31
315	110.48	332	46.30	349	3.17
320	186.47	333	51.82	350	5.51
325	304.20	334	57.67	351	8.33
330	461.77	335	63.77	352	11.94
335	676.03	336	70.09	353	16.77
340	934.21	337	76.59	354	23.57
		338	83.26	355	33.04
		339	90.22	356	45.07
		340	97.45	357	65.66
		341	105.06	358	86.50
		342	112.68	359	107.61
				360	128.98

2.4 DISCHARGE RATING CURVES

Each of the three dams has both a principal spillway and an emergency spillway. Information regarding the dimensions and elevations of each of these spillways was taken from a combination of original construction drawings, recent survey, and detailed descriptions from AEP personnel. Detailed calculations for the discharge rating curves of each spillway are included in Appendix B.

The principal spillway for the Primary Ash Pond is located in the canal connecting the Primary and Secondary Ash Ponds. It consists of a weir box with bottom elevation of 325.0 ft-msl and a 4-foot wide by 2-foot tall opening. Stop logs are placed in this opening according to regular dredging operations by AEP; however, normal conditions dictate that no stop logs are in place. This structure also consists of sheet piling to each side of the weir box, which will operate as a sharp-crested weir when flows reach the top elevation of 336.0 ft-msl. Additionally, the Primary Ash Pond has a 90-foot wide emergency spillway with a crest elevation of 334.0 ft-msl. Both the orifice and weir equations were utilized in calculating the discharge rating curves. The discharge rating curve for both spillways is shown in Table 4.

The principal spillway for the Secondary Ash Pond consists of a weir box with a 4-foot long weir discharging through a 36-inch conduit. The weir equation used for this weir box was obtained from Greg Carter of AEP from calculations he had performed in the design of a new weir plate, which is currently in place. Additionally, the Secondary Ash Pond has an approximately 45-foot wide earthen emergency spillway. The discharge rating curve for the emergency spillway was calculated with a simple HEC-RAS model with cross-sections cut through the spillway. The discharge rating curve for both spillways is shown in Table 4.

The principal spillway for the Bottom Ash Pond is a 40-foot long broad-crested weir with 6:1 side slopes and crest at elevation 355.0 ft-msl. It discharges into a small sump area connected to the 30-inch pipe directing flow back toward the Ash Storage Area. The emergency spillway is an 8-foot wide weir at elevation 358.0 ft-msl with a rock riprap discharge chute. The discharge rating curve for both spillways is shown in Table 4.

Table 4 - Discharge Rating Curves

Primary			
Elevation (ft-msl)	Principal Spillway (cfs)	Emergency Spillway (cfs)	Total Discharge (cfs)
325	0	---	0
326	39	---	39
327	54	---	54
328	67	---	67
329	77	---	77
330	86	---	86
331	94	---	94
332	102	---	102
333	109	---	109
334	116	0	116
335	122	285	407
336	128	849	976
337	340	1,637	1,977
338	723	2,640	3,363
339	1,217	3,857	5,074
340	1,801	5,291	7,092

Secondary			
Elevation (ft-msl)	Principal Spillway (cfs)	Emergency Spillway (cfs)	Total Discharge (cfs)
328.3	0	---	0
329	5	---	5
330	17	---	17
331	33	---	33
332	50	0	50
333	58	91	149
334	64	345	409
335	70	777	847
336	75	1,386	1,461
337	80	2,191	2,271
338	85	3,163	3,248
339	90	4,256	4,346
340	94	5,280	5,374

Bottom Ash			
Elevation (ft-msl)	Principal Spillway (cfs)	Emergency Spillway (cfs)	Total Discharge (cfs)
355.0	0	---	0
355.5	50	---	50
356.0	161	---	161
356.5	330	---	330
357.0	561	---	561
357.5	858	---	858
358.0	1,224	0	1,224
358.5	1,664	11	1,676
359.0	2,182	39	2,221
359.5	2,782	85	2,867
360.0	3,466	153	3,619

2.5 FREQUENCY MODEL RESULTS

Three frequency storm events were analyzed for the Welsh Ash Pond system – the 10-year, 25-year, and 100-year storm events. The hydrologic model described in the preceding sections was implemented in analyzing these events. Curve numbers were set to Antecedent Moisture Condition II, and initial abstractions were calculated automatically by HEC-HMS. These assumptions represent normal conditions, as would be expected prior to one of these storm events. The precipitation data was obtained from the National Oceanic and Atmospheric Administration’s Technical Memorandum NWS HYDRO-35⁴ and Technical Paper 40.⁵ These values are presented in Table 5. Each storm event was assumed to have a duration of 24 hours.

Table 5 – Frequency Precipitation Depths

Frequency (yrs)	Precipitation (in)							
	5 min	15 min	60 min	2 hr	3 hr	6 hr	12 hr	24hr
1	0.42	0.89	1.69	1.99	2.20	2.64	3.12	3.58
2	0.51	1.08	1.97	2.45	2.68	3.19	3.78	4.41
5	0.58	1.25	2.54	3.14	3.40	4.15	4.92	5.81
10	0.64	1.38	2.91	3.64	3.95	4.90	5.90	6.82
25	0.72	1.57	3.36	4.22	4.62	5.73	6.76	7.90
50	0.79	1.72	3.75	4.75	5.18	6.41	7.74	8.83
100	0.86	1.88	4.13	5.23	5.78	7.09	8.62	9.85
500	1.12	2.45	5.39	6.83	7.54	9.26	11.26	12.86

These precipitation depths serve as input data into the hydrologic model, and were routed through the model as described previously. According to TCEQ recommendations and standard engineering practice, flood routings were started at the lowest spillway crest elevation for each dam. This corresponds to elevation 325.0 ft-msl, 328.3 ft-msl, and 355.0 ft-msl for the Primary, Secondary, and Bottom Ash Ponds, respectively. The results of the 10-year, 25-year, and 100-year storm events are shown in Tables 6, 7, and 8, respectively.

Table 6 – 10-Year Storm Results

	Peak Elevation (ft-msl)	Peak Inflow (cfs)	Peak Outflow (cfs)
Primary	328.50	874.71	71.92
Secondary	332.37	112.41	72.35
Bottom Ash	355.53	157.81	55.99

Table 7 – 25-Year Storm Results

	Peak Elevation (ft-msl)	Peak Inflow (cfs)	Peak Outflow (cfs)
Primary	329.35	1079.37	80.24
Secondary	332.51	137.68	81.67
Bottom Ash	355.62	187.44	76.21

Table 8 – 100-Year Storm Results

	Peak Elevation (ft-msl)	Peak Inflow (cfs)	Peak Outflow (cfs)
Primary	330.80	1415.75	92.68
Secondary	332.62	177.95	95.96
Bottom Ash	355.76	234.22	108.10

2.6 PMF MODEL RESULTS

The Probable Maximum Flood (PMF) is defined as the greatest flood to be expected, and the Probable Maximum Precipitation (PMP) is theoretically the greatest depth of rainfall for a given duration that is physically possible over a given size storm area at a particular geographic location. Generally, the rainfall depth is calculated for the ten square miles of the watershed which receive the highest intensity rainfall.

Hydrometeorological Report No. 52 (HMR-52),⁶ developed by the U.S. Army Corps of Engineers, was used to determine the rainfall for each basin. PMP estimates were taken from Hydrometeorological Report No. 51⁷ and distributed according to HMR-52 to obtain average rainfall depths over the various drainage areas.

HMR-52 calculates rainfall depths for storm durations ranging from five minutes to seventy-two hours. Table 9 lists the point rainfall depths calculated by HMR-52 for storm durations from one hour to 72 hours. Because the total drainage area is less than ten square miles, these point rainfall depths were applied to each of the 7 basins. Additionally, the total rainfall depth was distributed according to the temporal distribution described by the TCEQ guidelines.

Table 9 – HMR-52 Point Rainfall Depths

Storm Duration (hr)	Depth (in)
1	16.62
2	20.86
3	24.18
6	30.47
12	36.82
24	42.10
48	46.98
72	49.74

Each PMF duration was modeled as described previously, with flood routing started at the lowest spillway crest elevation. The 12-hour event was critical for both the Primary and Secondary Ash Ponds, and the 1-hour event was critical for the Bottom Ash Pond. Additionally, the 25% and 50% PMF were calculated for the critical duration. Tables 10, 11, and 12 contain the results of these PMF model runs – the 25% PMF, 50% PMF, and 100% PMF, respectively.

Table 10 – 25% PMF Results

	Peak Elevation (ft-msl)	Peak Inflow (cfs)	Peak Outflow (cfs)
Primary	331.83	690.29	100.59
Secondary	332.68	110.63	105.57
Bottom Ash	355.70	171.14	94.27

Table 11 – 50% PMF Results

	Peak Elevation (ft-msl)	Peak Inflow (cfs)	Peak Outflow (cfs)
Primary	335.16	1385.23	122.79
Secondary	334.23	511.60	501.07
Bottom Ash	356.15	342.28	211.11

Table 12 – 100% PMF Results

	Peak Elevation (ft-msl)	Peak Inflow (cfs)	Peak Outflow (cfs)
Primary	337.46	2770.78	517.89
Secondary	337.39	2664.30	2637.73
Bottom Ash	356.78	684.55	458.48

3.0 SUMMARY AND CONCLUSIONS

Based on the results of the hydraulic analysis, each of the three dams is hydraulically adequate for the full range of storm events from the 10-year to the 100% PMF event. Table 13 lists the pertinent elevation data for each dam, including the top of dam elevation and principal and emergency spillway crest elevations. Comparing these elevations to the maximum water surface elevations shown in Table 14 indicates that, even during the 100% PMF event, each of the three dams would have almost 3 feet of freeboard. Additionally, the emergency spillway for the Primary Ash Pond is not engaged during a storm event less than the 50% PMF, and the emergency spillway for the Bottom Ash Pond is not engaged, even during the 100% PMF event. The emergency spillway for the Secondary Ash Pond is, however, engaged much more frequently, even during a storm event as low as the 10-year storm. This should have no adverse affects on this area though, as it appears to have been designed to withstand frequent engaging.

Table 13 – Pertinent Dam Information

	Top of Dam (ft-msl)	Principal Spillway (ft-msl)	Emergency Spillway (ft-msl)
Primary	340.0	325.0	334.0
Secondary	340.0	328.3	332.0
Bottom Ash	360.0	355.0	358.0

Table 14 – Summary of Results

	10-year	25-year	100-year	25% PMF	50% PMF	100% PMF
Primary	328.50	329.35	330.80	331.83	335.16	337.46
Secondary	332.37	332.51	332.62	332.68	334.23	337.39
Bottom Ash	355.53	355.62	355.76	355.70	356.15	356.78

It should be noted that these results reflect the best understanding of existing conditions and could be significantly affected by major changes to any of the three reservoirs. Specifically, major fluctuations in the available storage in each reservoir, as could be caused by the regular dredging and movement of bottom ash in and out of the pond areas, would greatly impact the results of this analysis. However, in their current conditions, the Primary Ash, Secondary Ash, and Bottom Ash Ponds associated with the Welsh Power Plant are deemed to



be hydraulically adequate for any storm event up to the 100% PMF. Pertinent drawings for existing conditions are included in Appendix C.

Appendix A References

References

1. U.S. Army Corps of Engineers, Hydrologic Engineering Center: *Hydrologic Modeling System HEC-HMS - User's Manual Version 3.4*, Davis, California, August 2009.
2. "Soil Data Mart." *NRCS Soil Survey Geographic (SSURGO) Database*. <<http://soildatamart.nrcs.usda.gov>>.
3. "National Land Cover Dataset 2001." *USGS Seamless Data Warehouse*. August 30, 2010. <<http://seamless.usgs.gov/nlcd.php>>.
4. U.S. Department of Commerce, National Oceanic and Atmospheric Administration: *Technical Memorandum NWS HYDRO-35, Five- to 60-Minute Precipitation Frequency for the Eastern and Central United States*, Silver Spring, MD, June 1977.
5. U.S. Department of Commerce, Weather Bureau: *Technical Paper No. 40, Rainfall Frequency Atlas of the United States for Durations from 30 Minutes to 24 Hours and Return Periods from 1 to 100 Years*, Washington, D.C., May 1961.
6. U.S. Department of Commerce, National Oceanic and Atmospheric Administration and U.S. Department of the Army, Corps of Engineers: *Hydrometeorological Report No. 52, Application of Probable Maximum Precipitation Estimates, United States East of the 105th Meridian*, Washington, D.C., 1982.
7. U.S. Department of Commerce, National Oceanic and Atmospheric Administration and U.S. Department of the Army, Corps of Engineers: *Hydrometeorological Report No. 51, Probable Maximum Precipitation Estimates, United States East of the 105th Meridian*, Washington, D.C., 1978.

Appendix B Calculations

Discharge Rating Curve
Primary Ash Pond

Elevation [ft-msl]	Orifice [cfs]	Sheet Pile [cfs]	Main [cfs]	Emerg [cfs]	Total [cfs]
325.00	0.00	0.00	0.00	0.00	0.00
326.00	38.52	0.00	38.52	0.00	38.52
327.00	54.48	0.00	54.48	0.00	54.48
328.00	66.72	0.00	66.72	0.00	66.72
329.00	77.04	0.00	77.04	0.00	77.04
330.00	86.13	0.00	86.13	0.00	86.13
331.00	94.35	0.00	94.35	0.00	94.35
332.00	101.91	0.00	101.91	0.00	101.91
333.00	108.95	0.00	108.95	0.00	108.95
334.00	115.56	0.00	115.56	0.00	115.56
335.00	121.81	0.00	121.81	285.00	406.81
336.00	127.76	0.00	127.76	848.53	976.28
337.00	133.44	206.46	339.90	1636.79	1976.68
338.00	138.89	583.96	722.84	2640.00	3362.84
339.00	144.13	1072.80	1216.93	3857.22	5074.14
340.00	149.19	1651.68	1800.87	5290.90	7091.76

Main Spillway

Sill Crest 325 ft-msl
 Height 2 ft
 Sill Width 4 ft
 Orifice C 0.6

$$Q = C * A * \sqrt{2 * g * H}$$

Sheet Pile 336 ft-msl
 Top Width 62 ft
 Weir C 3.33

$$Q = C * L * H^{3/2}$$

Emergency Spillway

Crest 334 ft-msl
 Length 90 ft
 SS 2.5 :1
 Weir C 3

$$Q = C * (L + 2 * SS * H) * H^{3/2}$$

Discharge Rating Curve
Secondary Ash Pond

Elevation [ft-msl]	Weir [cfs]	Conduit [cfs]	Main [cfs]	Emerg [cfs]	Total [cfs]
328.30	0.00	12.77	0.00		0.00
328.50	0.75	15.39	0.75		0.75
329.00	4.85	22.36	4.85		4.85
329.50	10.62	29.44	10.62		10.62
330.00	17.43	35.94	17.43		17.43
330.50	24.97	40.33	24.97		24.97
331.00	33.01	44.34	33.01		33.01
331.50	41.36	48.10	41.36		41.36
332.00	49.90	51.65	49.90	0.00	49.90
332.50	58.50	55.03	55.03	25.00	80.03
333.00	67.07	58.27	58.27	90.91	149.18
333.50	75.51	61.37	61.37	193.62	254.99
334.00	83.73	64.36	64.36	344.83	409.19
334.50	91.67	67.24	67.24	537.74	604.98
335.00	99.25	70.03	70.03	777.17	847.20
335.50	106.41	72.72	72.72	1056.25	1128.97
336.00	113.09	75.34	75.34	1385.71	1461.05
336.50	119.24	77.87	77.87	1769.84	1847.71
337.00	124.79	80.34	80.34	2190.91	2271.25
337.50	129.70	82.74	82.74	2656.86	2739.60
338.00	133.91	85.08	85.08	3163.04	3248.12
338.50	137.39	87.36	87.36	3697.92	3785.28
339.00	140.09	89.59	89.59	4256.10	4345.69
339.50	141.96	91.76	91.76	4767.86	4859.62
340.00	142.96	93.89	93.89	5279.62	5373.51

Main Spillway
Weir Box

Crest 328.30 ft-msl
 Length 4 ft
 Weir C 2.152

$$Q = C*(L-0.2H)*H^{1/2}$$

Weir Equation from AEP

Conduit

Diameter 36 in
 Length 350 ft
 U/S Invert 326.5 ft-msl
 D/S Invert 326 ft-msl


Calculated in FlowMaster

Emergency Spillway

Calculated in HEC-RAS; refer to following sheets for details.

Invert 332 Feet msl
Increment 0.5 Feet

Lake Level (feet msl)	Discharge (cfs)
332.00	0
332.50	25
333.00	91
333.50	194
334.00	345
334.50	538
335.00	777
335.50	1,056
336.00	1,386
336.50	1,770
337.00	2,191
337.50	2,657
338.00	3,163
338.50	3,698
339.00	4,256
339.50	4,768
340.00	5,280



HEC-RAS Results for most upstream cross section

River	Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude #	Chl
SecondaryPon	EmergSpwy	871	PF 1	1	330	332.07		332.07	0	0	380.1	195.63	0	
SecondaryPon	EmergSpwy	871	PF 2	10	330	332.29		332.29	0	0.02	423.67	197.71	0	
SecondaryPon	EmergSpwy	871	PF 3	25	330	332.5		332.5	0.000002	0.06	465.34	200.66	0.01	
SecondaryPon	EmergSpwy	871	PF 4	50	330	332.73		332.73	0.000005	0.1	511.65	204.53	0.01	
SecondaryPon	EmergSpwy	871	PF 5	100	330	333.06		333.06	0.000012	0.18	579.79	208.93	0.02	
SecondaryPon	EmergSpwy	871	PF 6	200	330	333.52		333.53	0.000031	0.32	677.95	215.13	0.03	
SecondaryPon	EmergSpwy	871	PF 7	300	330	333.87		333.87	0.000051	0.43	752.96	221.16	0.04	
SecondaryPon	EmergSpwy	871	PF 8	400	330	334.16		334.16	0.000071	0.54	818.24	228.29	0.05	
SecondaryPon	EmergSpwy	871	PF 9	500	330	334.41		334.42	0.000091	0.64	876.57	234.47	0.05	
SecondaryPon	EmergSpwy	871	PF 10	750	330	334.94		334.95	0.00014	0.85	1005.18	248.81	0.07	
SecondaryPon	EmergSpwy	871	PF 11	1000	330	335.4		335.41	0.000184	1.03	1120.39	261.11	0.08	
SecondaryPon	EmergSpwy	871	PF 12	1250	330	335.79		335.81	0.000224	1.19	1225.76	271.83	0.09	
SecondaryPon	EmergSpwy	871	PF 13	1500	330	336.14		336.16	0.000261	1.34	1322.88	281.28	0.1	
SecondaryPon	EmergSpwy	871	PF 14	2000	330	336.77		336.79	0.000326	1.6	1503.25	297.77	0.11	
SecondaryPon	EmergSpwy	871	PF 15	2500	330	337.31		337.34	0.000381	1.82	1668.85	312.15	0.12	
SecondaryPon	EmergSpwy	871	PF 16	3000	330	337.81		337.85	0.000427	2.01	1827.39	325.32	0.13	
SecondaryPon	EmergSpwy	871	PF 17	3500	330	338.26		338.31	0.000468	2.19	1978.88	337.7	0.13	
SecondaryPon	EmergSpwy	871	PF 18	4000	330	338.73		338.79	0.000495	2.34	2139.91	350.57	0.14	
SecondaryPon	EmergSpwy	871	PF 19	4500	330	339.13		339.2	0.000525	2.48	2282.96	361.62	0.14	
SecondaryPon	EmergSpwy	871	PF 20	5000	330	339.69		339.76	0.000513	2.55	2489.43	376.54	0.14	

Discharge Rating Curve
Bottom Ash Pond

Elevation [ft-msl]	Main [cfs]	Emerg [cfs]	Total [cfs]
355.00	0.00	0.00	0.00
355.50	50.42	0.00	50.42
356.00	161.20	0.00	161.20
356.50	330.31	0.00	330.31
357.00	561.16	0.00	561.16
358.00	1224.21	0.00	1224.21
359.00	2182.40	39.00	2221.40
360.00	3465.91	152.74	3618.64
361.00	5102.78	358.53	5461.31
362.00	7119.19	672.00	7791.19
363.00	9539.72	1106.85	10646.57

Main Spillway

Crest 355 ft-msl
 Length 40 ft
 SS 6 :1
 Weir C 3.1

$$Q = C*(L+2*SS*H)*H^{3/2}$$

Emergency Spillway

Crest 358 ft-msl
 Length 8 ft
 SS 2.5 :1
 Weir C 3

$$Q = C*(L+2*SS*H)*H^{3/2}$$

Name	GRIDCODE	HSG	Area_ft^2	Area_acre	CN	Inc. CN
Ash Storage	31	C	1324276.445	30.401	91	70.06793
Ash Storage	42	C	53818.662	1.236	73	2.28431
Ash Storage	81	C	341795.137	7.847	74	14.70608
Bottom Ash	31	C	948778.856	21.781	91	91
Power Plant	41	B	1095.992	0.025	60	0.013099
Power Plant	42	B	101918.155	2.340	60	1.218085
Power Plant	81	B	99556.094	2.285	61	1.209685
Power Plant	22	C	15964.935	0.367	79	0.251229
Power Plant	23	C	70296.650	1.614	90	1.260236
Power Plant	24	C	2954103.082	67.817	94	55.31313
Power Plant	41	C	90963.024	2.088	73	1.322703
Power Plant	42	C	239129.961	5.490	73	3.477215
Power Plant	52	C	407500.071	9.355	70	5.68199
Power Plant	81	C	944143.815	21.675	74	13.91697
Power Plant	82	C	95577.482	2.194	85	1.618263
Primary	11	W	458394.580	10.523	100	4.490426
Primary	31	W	14036.955	0.322	100	0.137506
Primary	42	W	104596.947	2.401	100	1.02463
Primary	52	W	11325.853	0.260	100	0.110948
Primary	81	W	69931.187	1.605	100	0.685045
Primary	22	B	242034.352	5.556	68	1.612256
Primary	41	B	564582.710	12.961	60	3.318386
Primary	42	B	631114.853	14.488	60	3.709435
Primary	52	B	220919.125	5.072	56	1.211907
Primary	81	B	286358.868	6.574	61	1.711152
Primary	11	C	480754.464	11.037	100	4.709463
Primary	22	C	209907.569	4.819	79	1.624438
Primary	23	C	10746.609	0.247	90	0.094746
Primary	24	C	67309.636	1.545	94	0.619802
Primary	31	C	150242.962	3.449	91	1.339318
Primary	41	C	540228.652	12.402	73	3.863212
Primary	42	C	316050.970	7.256	73	2.260102
Primary	43	C	93028.069	2.136	73	0.66525
Primary	52	C	572546.147	13.144	70	3.926057
Primary	81	C	1192671.364	27.380	74	8.645709
Primary	82	C	10291.113	0.236	85	0.08569
Primary	90	C	82404.904	1.892	77	0.621573
Primary	41	C/D	916028.058	21.029	76	6.819781
Primary	42	C/D	135572.435	3.112	76	1.00933
Primary	52	C/D	331086.513	7.601	74	2.383839
Primary	90	C/D	101862.212	2.338	80	0.798273
Primary	22	D	301628.331	6.924	84	2.481987
Primary	31	D	13591.654	0.312	94	0.125155
Primary	41	D	558509.208	12.822	79	4.322207
Primary	42	D	58185.234	1.336	79	0.450286
Primary	43	D	21907.998	0.503	79	0.169542
Primary	52	D	973523.140	22.349	77	7.343195
Primary	81	D	435789.772	10.004	80	3.415192
Primary	90	D	31102.113	0.714	83	0.252881
Secondary	11	W	61159.403	1.404	100	8.574385
Secondary	22	W	0.178	0.000	100	2.49E-05
Secondary	24	W	284.987	0.007	100	0.039954
Secondary	52	W	3328.994	0.076	100	0.466716
Secondary	81	W	66883.300	1.535	100	9.37686
Secondary	11	C	100304.658	2.303	100	14.06244
Secondary	22	C	7813.937	0.179	79	0.865439
Secondary	23	C	5348.021	0.123	90	0.6748
Secondary	24	C	9873.918	0.227	94	1.301239
Secondary	31	C	300.129	0.007	91	0.03829
Secondary	42	C	37168.223	0.853	73	3.803946
Secondary	52	C	28941.171	0.664	70	2.840232
Secondary	81	C	391873.463	8.996	74	40.65531
to Bottom Ash	22	C	173034.687	3.972	79	17.29527

Basin	Area_acre
Ash Storage	39.48
Bottom Ash	21.78
Power Plant	115.25
Primary	234.35
Secondary	16.37
to Bottom Ash	18.14

BASIN LAG TIME CALCULATION
USING NRCS TR55 METHOD TO COMPUTE TIME OF CONCENTRATION

Existing Conditions

Project Data:		Comments:			
PROJECT	AEP10412				
LOCATION	Welsh Power Plant				
DATE	Dec-10				
BASIN COND.					
BY:	JPM				
WSHED NAME	Ash Storage A				

SHEET FLOW: (100' MAX)

Land Use	n value	% Land use	Inc n
Undeveloped			
Conc., gravel, asphalt, bare soil	0.015	100	0.015
Grass Short Prairie	0.15	0	0
Maintained Grass	0.03	0	0
Woods Light Underbrush	0.4	0	0
Woods Dense underbrush	0.8	0	0
TOTAL		100	0.015

LENGTH	100	FT.	MAX 100'
2 YR. 24 HOUR PRECIP	4.31	IN.	
SLOPE	0.010	FT/FT	

$$T_1 = 0.007 \times \frac{(n \times L)^{0.8}}{R^{0.5} \times S^{0.4}}$$

SHALLOW CONCENTRATED FLOW

1=PAVED 2=UNPAVED	2	
LENGTH	919.70	FT
SLOPE	0.021	FT/FT
COMPUTED VELOCITY FROM FIGURE 3.1	2.319	

$$T_2 = \frac{L}{60 \times V}$$

PIPE FLOW - SOLVE FOR FULL FLOW VELOCITY

DIAMETER =	36	IN.
XSECT AREA =	7.07	SQ FT
WETTED PERIMETER	9.42	FT
SLOPE	0.002	FT/FT
MANNINGS N	0.024	
COMPUTED VELOCITY	2.39	FT/S
LENGTH	60	FT

$$V = \frac{1.49 \times \left(\frac{a}{p_w}\right)^{\frac{2}{3}} \times s^{\frac{1}{2}}}{n}$$

$$T_4 = \frac{L}{60 \times V}$$

WATERSHED NUMBER	Conditions	Adjusted Tc (Min)	NRCS Method Tc (Min)	Selected Tc (Min)
Ash Storage A				
SHEET FLOW	Max 30 Min	30.0	1.77	1.77
SHALLOW CONCENTRATED FLOW			6.61	6.61
SHALLOW CONCENTRATED FLOW			0.00	0.00
SHALLOW CHANNEL FLOW				0.00
PIPE FLOW			0.42	0.42
CHANNEL FLOW				0.00
TOTAL			8.79	8.79
			Lag (Hrs) =	0.09

$$T_c = T_1 + T_2 + T_3 + T_4 + T_5 + T_6$$

Lag(min) = 5.28

BASIN LAG TIME CALCULATION
USING NRCS TR55 METHOD TO COMPUTE TIME OF CONCENTRATION

Existing Conditions

Project Data:		Comments:			
PROJECT	AEP10412				
LOCATION	Welsh Power Plant				
DATE	Dec-10				
BASIN COND.					
BY:	JPM				
WSHED NAME	Ash Storage B				

SHEET FLOW: (100' MAX)

Land Use	n value	% Land use	Inc n
Undeveloped			
Conc., gravel, asphalt, bare soil	0.015	100	0.015
Grass Short Prairie	0.15	0	0
Maintained Grass	0.03	0	0
Woods Light Underbrush	0.4	0	0
Woods Dense underbrush	0.8	0	0
TOTAL		100	0.015

LENGTH	100	FT.	MAX 100'
2 YR. 24 HOUR PRECIP	4.31	IN.	
SLOPE	0.025	FT/FT	

$$T_1 = 0.007 \times \frac{(n \times L)^{0.8}}{R^{0.5} \times S^{0.4}}$$

SHALLOW CONCENTRATED FLOW

1=PAVED 2=UNPAVED	2	
LENGTH	796.31	FT
SLOPE	0.020	FT/FT
COMPUTED VELOCITY FROM FIGURE 3.1	2.287	

$$T_2 = \frac{L}{60 \times V}$$

CHANNEL FLOW

XSECT AREA=	112.000	SQ FT	TOPWIDTH	50
			BOTTOM	6
			DEPTH	4
WETTED PERIMETER	50.721	FT		
SLOPE	0.008	FT/FT		
MANNINGS N	0.08			
COMPUTED VELOCITY	2.768	FT/S		
LENGTH	911.59	FT		

$$V = \frac{1.49 \times \left(\frac{a}{p_w}\right)^{\frac{2}{3}} \times s^{\frac{1}{2}}}{n}$$

$$T_6 = \frac{L}{60 \times V}$$

Conditions	Adjusted	NRCS Method	Selected
WATERSHED NUMBER	Tc (Min)	Tc (Min)	Tc (Min)
Ash Storage B			
SHEET FLOW	Max 30 Min	30.0	1.22
SHALLOW CONCENTRATED FLOW			5.80
CHANNEL FLOW			5.49
TOTAL			12.52
		Lag (Hrs) =	0.13

$$T_c = T_1 + T_2 + T_3 + T_4 + T_5 + T_6$$

Lag(min) = 7.51

BASIN LAG TIME CALCULATION
 USING NRCS TR55 METHOD TO COMPUTE TIME OF CONCENTRATION

Existing Conditions

Project Data:		Comments:			
PROJECT	AEP10412				
LOCATION	Welsh Power Plant				
DATE	Dec-10				
BASIN COND.					
BY:	JPM				
WSHED NAME	Bottom Ash				

SHEET FLOW: (100' MAX)			
Land Use	n value	% Land use	Inc n
Conc.,gravel,asphalt,bare soil	0.015	100	0.015
Grass Short Prairie	0.15	0	0
Maintained Grass	0.03	0	0
Woods Light Underbrush	0.4	0	0
Woods Dense underbrush	0.8	0	0
TOTAL		100	0.015

LENGTH	100	FT.	MAX 100'
2 YR. 24 HOUR PRECIP	4.31	IN.	
SLOPE	0.020	FT/FT	

$$T_1 = 0.007 \times \frac{(n \times L)^{0.8}}{R^{0.5} \times S^{0.4}}$$

SHALLOW CONCENTRATED FLOW			
1=PAVED 2=UNPAVED	LENGTH	SLOPE	COMPUTED VELOCITY FROM FIGURE 3.1=
2	627.21	0.010	1.578
		FT/FT	

$$T_2 = \frac{L}{60 \times V}$$

Conditions	Adjusted	NRCS Method	Selected
WATERSHED NUMBER	Tc (Min)	Tc (Min)	Tc (Min)
Bottom Ash			
SHEET FLOW	Max 30 Min	30.0	1.34
SHALLOW CONCENTRATED FLOW			6.62
TOTAL			7.96
		Lag (Hrs) =	0.08

$$T_c = T_1 + T_2 + T_3 + T_4 + T_5 + T_6$$

Lag(min) = 4.78

984.648438

BASIN LAG TIME CALCULATION
USING NRCS TR55 METHOD TO COMPUTE TIME OF CONCENTRATION

Existing Conditions

Project Data:		Comments:			
PROJECT	AEP10412				
LOCATION	Welsh Power Plant				
DATE	Dec-10				
BASIN COND.					
BY:	JPM				
WSHED NAME	Power Plant				

SHEET FLOW: (100' MAX)

Land Use	n value	% Land use	Inc n
Undeveloped			
Conc., gravel, asphalt, bare soil	0.015	0	0
Grass Short Prairie	0.15	0	0
Maintained Grass	0.03	0	0
Woods Light Underbrush	0.4	100	0.4
Woods Dense underbrush	0.8	0	0
TOTAL		100	0.4

LENGTH	100	FT.	MAX 100'
2 YR. 24 HOUR PRECIP	4.31	IN.	
SLOPE	0.020	FT/FT	

$$T_1 = 0.007 \times \frac{(n \times L)^{0.8}}{R^{0.5} \times S^{0.4}}$$

SHALLOW CONCENTRATED FLOW

1=PAVED 2=UNPAVED	2	
LENGTH	558.86	FT
SLOPE	0.036	FT/FT
COMPUTED VELOCITY FROM FIGURE 3.1	3.052	

$$T_2 = \frac{L}{60 \times V}$$

CHANNEL FLOW

XSECT AREA=	8.000	SQ FT	TOPWIDTH	7
			BOTTOM	1
			DEPTH	2
WETTED PERIMETER	8.211	FT		
SLOPE	0.016	FT/FT		
MANNINGS N	0.05			
COMPUTED VELOCITY	3.720	FT/S		
LENGTH	2169.79	FT		

$$V = \frac{1.49 \times \left(\frac{a}{p_w}\right)^{\frac{2}{3}} \times s^{\frac{1}{2}}}{n}$$

$$T_6 = \frac{L}{60 \times V}$$

WATERSHED NUMBER	Conditions	Adjusted Tc (Min)	NRCS Method Tc (Min)	Selected Tc (Min)
Power Plant				
SHEET FLOW	Max 30 Min	30.0	18.50	18.50
SHALLOW CONCENTRATED FLOW			3.05	3.05
CHANNEL FLOW			9.72	9.72
TOTAL			31.28	31.28
			Lag (Hrs) =	0.31

$$T_c = T_1 + T_2 + T_3 + T_4 + T_5 + T_6$$

Lag(min) = 18.77

BASIN LAG TIME CALCULATION
USING NRCS TR55 METHOD TO COMPUTE TIME OF CONCENTRATION

Existing Conditions

Project Data:		Comments:			
PROJECT	AEP10412				
LOCATION	Welsh Power Plant				
DATE	Dec-10				
BASIN COND.					
BY:	JPM				
WSHED NAME	Primary				

SHEET FLOW: (100' MAX)

Land Use	n value	% Land use	Inc n
Undeveloped			
Conc., gravel, asphalt, bare soil	0.015	0	0
Grass Short Prairie	0.15	0	0
Maintained Grass	0.03	0	0
Woods Light Underbrush	0.4	100	0.4
Woods Dense underbrush	0.8	0	0
TOTAL		100	0.4

LENGTH	100	FT.	MAX 100'
2 YR. 24 HOUR PRECIP	4.31	IN.	
SLOPE	0.020	FT/FT	

$$T_1 = 0.007 \times \frac{(n \times L)^{0.8}}{R^{0.5} \times S^{0.4}}$$

SHALLOW CONCENTRATED FLOW

1=PAVED 2=UNPAVED	2	
LENGTH	2757.28	FT
SLOPE	0.009	FT/FT
COMPUTED VELOCITY FROM FIGURE 3.1	1.536	

$$T_2 = \frac{L}{60 \times V}$$

CHANNEL FLOW

XSECT AREA	18.000	SQ FT	TOPWIDTH	10
			BOTTOM	2
			DEPTH	3
WETTED PERIMETER	12.000	FT		
SLOPE	0.010	FT/FT		
MANNINGS N	0.07			
COMPUTED VELOCITY	2.800	FT/S		
LENGTH	1984.65	FT		

$$V = \frac{1.49 \times \left(\frac{a}{p_w}\right)^{\frac{2}{3}} \times s^{\frac{1}{2}}}{n}$$

$$T_6 = \frac{L}{60 \times V}$$

WATERSHED NUMBER	Conditions	Adjusted Tc (Min)	NRCS Method Tc (Min)	Selected Tc (Min)
Primary				
SHEET FLOW	Max 30 Min	30.0	18.50	18.50
SHALLOW CONCENTRATED FLOW			29.91	29.91
CHANNEL FLOW			11.81	11.81
TOTAL			60.23	60.23
			Lag (Hrs) =	0.60

$$T_c = T_1 + T_2 + T_3 + T_4 + T_5 + T_6$$

Lag(min) = 36.14

BASIN LAG TIME CALCULATION
USING NRCS TR55 METHOD TO COMPUTE TIME OF CONCENTRATION

Existing Conditions

Project Data:		Comments:			
PROJECT	AEP10412				
LOCATION	Welsh Power Plant				
DATE	Dec-10				
BASIN COND.					
BY:	JPM				
WSHED NAME	Secondary				

SHEET FLOW: (100' MAX)

Land Use	n value	% Land use	Inc n
Undeveloped			
Conc., gravel, asphalt, bare soil	0.015	100	0.015
Grass Short Prairie	0.15	0	0
Maintained Grass	0.03	0	0
Woods Light Underbrush	0.4	0	0
Woods Dense underbrush	0.8	0	0
TOTAL		100	0.015

LENGTH	100	FT.	MAX 100'
2 YR. 24 HOUR PRECIP	4.31	IN.	
SLOPE	0.150	FT/FT	

$$T_1 = 0.007 \times \frac{(n \times L)^{0.8}}{R^{0.5} \times S^{0.4}}$$

SHALLOW CONCENTRATED FLOW

1=PAVED 2=UNPAVED	2	
LENGTH	599.56	FT
SLOPE	0.036	FT/FT
COMPUTED VELOCITY FROM FIGURE 3.1	3.070	

$$T_2 = \frac{L}{60 \times V}$$

Conditions	Adjusted	NRCS Method	Selected
WATERSHED NUMBER	Tc (Min)	Tc (Min)	Tc (Min)
Secondary			
SHEET FLOW	Max 30 Min	30.0	0.60
SHALLOW CONCENTRATED FLOW			3.26
TOTAL			3.85
		Lag (Hrs) =	0.04

$$T_c = T_1 + T_2 + T_3 + T_4 + T_5 + T_6$$

Lag(min) = 2.31

BASIN LAG TIME CALCULATION
USING NRCS TR55 METHOD TO COMPUTE TIME OF CONCENTRATION

Existing Conditions

Project Data:		Comments:			
PROJECT	AEP10412				
LOCATION	Welsh Power Plant				
DATE	Dec-10				
BASIN COND.					
BY:	JPM				
WSHED NAME	to Bottom Ash				

SHEET FLOW: (100' MAX)

Land Use	n value	% Land use	Inc n
Undeveloped			
Conc., gravel, asphalt, bare soil	0.015	0	0
Grass Short Prairie	0.15	0	0
Maintained Grass	0.03	0	0
Woods Light Underbrush	0.4	100	0.4
Woods Dense underbrush	0.8	0	0
TOTAL		100	0.4

LENGTH	100	FT.	MAX 100'
2 YR. 24 HOUR PRECIP	4.31	IN.	
SLOPE	0.050	FT/FT	

$$T_1 = 0.007 \times \frac{(n \times L)^{0.8}}{R^{0.5} \times S^{0.4}}$$

SHALLOW CONCENTRATED FLOW

1=PAVED 2=UNPAVED	2	
LENGTH	763.95	FT
SLOPE	0.004	FT/FT
COMPUTED VELOCITY FROM FIGURE 3.1	1.011	

$$T_2 = \frac{L}{60 \times V}$$

CHANNEL FLOW

XSECT AREA=	20.000	SQ FT	TOPWIDTH	16
			BOTTOM	4
			DEPTH	2
WETTED PERIMETER	16.649	FT		
SLOPE	0.008	FT/FT		
MANNINGS N	0.05			
COMPUTED VELOCITY	3.001	FT/S		
LENGTH	377.81	FT		

$$V = \frac{1.49 \times \left(\frac{a}{p_w}\right)^{\frac{2}{3}} \times s^{\frac{1}{2}}}{n}$$


$$T_6 = \frac{L}{60 \times V}$$

WATERSHED NUMBER	Conditions	Adjusted	NRCS Method	Selected
	to Bottom Ash	Tc (Min)	Tc (Min)	Tc (Min)
SHEET FLOW	Max 30 Min	30.0	12.83	12.83
SHALLOW CONCENTRATED FLOW			12.59	12.59
CHANNEL FLOW			2.10	2.10
TOTAL			27.52	27.52
			Lag (Hrs) =	0.28

$$T_c = T_1 + T_2 + T_3 + T_4 + T_5 + T_6$$

Lag(min) = 16.51

Appendix C Pertinent Drawings



ID	Description	Location	Size (Gallons)	SECONDARY CONTAINMENT (GALLONS)
1	Storage Tank	Intake	N/A	N/A
2	Chemical Building	W of Intake	4 - 1 ton cylinders	N/A
3	Emergency Diesel Pump	Plant House	500	500
4	Tractor Shop Diesel Tanks	500 Gallon transfer shed	5,000	4,375
5	Load Oil Tank	Inside containment area of tank house	5,000	1,100,400*
6	45 Fuel Oil Storage Tank	SE of Unit #1 Transformer	675,000	1,100,400*
7	Spill Transfer Pump Compartment	W of Spill Transformer	N/A	N/A
8	Oil House	NE of Unit #1	Variable	Variable
9	Fuel Oil collecting tank	SE of Fuel Oil Tank	N/A	6,000
10	Lighter Fuel Oil Pump Station	SE of Fuel Oil Tank	N/A	2,000
11	Spill Transfer Pump Station	Variable	Variable	N/A
12	Spill Transfer Pump Station	Variable	Variable	N/A
13	Clean & Dirty Oil Tanks	SE of Unit #1	2 @ 11,000 1 @ 2,000	3,300
14	Decontaminated Water Storage Tanks	NE of Unit #1	Variable	N/A
15	Filtered Water Tank	SE of Unit #1	75,000	N/A
16	Clarifier - Sodium Hydroxide	SE of Unit #1	15,000	3,700*
17	Clarifier - Alum	SE of Unit #1	15,000	3,700*
18	Clarifier - Sodium Hydroxide	SE of Unit #1	5,000	1,575*
19	Tractor Shop Oil	W of Tractor Shop	5,000	4,375
20	Turbine Oil Tanks	Inside Unit 1, 2 & 3 Turbine Buildings	Unit 2 - 7,000 Unit 3 - 7,000	Unit 2 - 1,750 Unit 3 - 1,750
21	Spill Transfer Pump Station	Phosphate Bldg. East Unit	N/A	N/A
22	Tractor Shop	Tractor Shop	N/A	N/A
23	Tractor Shop	Tractor Shop	N/A	N/A
24	Tractor Shop	Tractor Shop	N/A	N/A
25	Tractor Shop	Tractor Shop	N/A	N/A
26	Tractor Shop	Tractor Shop	N/A	N/A
27	Tractor Shop	Tractor Shop	N/A	N/A
28	Tractor Shop	Tractor Shop	N/A	N/A
29	Tractor Shop	Tractor Shop	N/A	N/A
30	Tractor Shop	Tractor Shop	N/A	N/A

ID	Description	Location	Size (Gallons)	SECONDARY CONTAINMENT (GALLONS)
31	CO2 Tank	Unit #2 Boiler Elevator	14 Tons	N/A
32	CO2 Tank	SE of Unit #2	14 Tons	N/A
33	CO2 Tank	W of Unit #1	14 Tons	N/A
34	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
35	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
36	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
37	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
38	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
39	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
40	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
41	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
42	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
43	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
44	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
45	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
46	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
47	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
48	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
49	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
50	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
51	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
52	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
53	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
54	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
55	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
56	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
57	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
58	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
59	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A
60	CO2 Tank	Unit #1 Boiler Elevator	14 Tons	N/A

ID	Description	Location	Size (Gallons)	SECONDARY CONTAINMENT (GALLONS)
61	Water Storage Intermediate	SE of Unit #1	Variable	N/A
62	Water Storage Intermediate	SE of Unit #1	Variable	N/A
63	Water Storage Intermediate	SE of Unit #1	Variable	N/A
64	Water Storage Intermediate	SE of Unit #1	Variable	N/A
65	Water Storage Intermediate	SE of Unit #1	Variable	N/A
66	Water Storage Intermediate	SE of Unit #1	Variable	N/A
67	Water Storage Intermediate	SE of Unit #1	Variable	N/A
68	Water Storage Intermediate	SE of Unit #1	Variable	N/A
69	Water Storage Intermediate	SE of Unit #1	Variable	N/A
70	Water Storage Intermediate	SE of Unit #1	Variable	N/A
71	Water Storage Intermediate	SE of Unit #1	Variable	N/A
72	Water Storage Intermediate	SE of Unit #1	Variable	N/A
73	Water Storage Intermediate	SE of Unit #1	Variable	N/A
74	Water Storage Intermediate	SE of Unit #1	Variable	N/A
75	Water Storage Intermediate	SE of Unit #1	Variable	N/A
76	Water Storage Intermediate	SE of Unit #1	Variable	N/A
77	Water Storage Intermediate	SE of Unit #1	Variable	N/A
78	Water Storage Intermediate	SE of Unit #1	Variable	N/A
79	Water Storage Intermediate	SE of Unit #1	Variable	N/A
80	Water Storage Intermediate	SE of Unit #1	Variable	N/A

* The total oil and coal oil tanks are located in a common shed area.
** Ash & Coals tanks have small separate containment (13,000 gal)

- STORM WATER OUTFALLS
- ⊗ S001
 - ⊗ S002
 - ⊗ S004
 - ⊗ MONITORING WELLS
 - ⊗ ASH POND MONITORING WELLS



- PLANT ROAD
- ⬮ FIRE HYDRANT
 - ⚠ EVACUATION AREA
 - ⚠ EVACUATION AREA
 - ⚠ EVACUATION AREA
 - ⚠ EVACUATION AREA

SWAUANO RESERVOIR

SWAUANO LAKE RESERVOIR
NORMAL POOL AL. 320'-0"
LOW WATER EL. 314'-0"
AREA = 1365 ACRES

MWO 007 Temporary Storage Frac Tanks
MWO 018 RCRA Exempt
MWO 019 Temporary Tank





REV	DESCRIPTION	DATE	DR	BY	APP
8	CONFORMS TO CONSTRUCTION RECORDS	5/2/07	ML		JM
10	FUTURE SITE AREAS	6/2/10	ML		MD
9	CONFORMS TO CONSTRUCTION RECORDS	9/25/08	ML		JM

SPCC & STORM WATER SITE PLAN
WELSH POWER PLANT
PITTSBURG, TEXAS

SOUTHWESTERN ELECTRIC POWER

DRAFTING/ENGINEERING DATE SCALE 1:1
DFT: M. LONG 9/19/00
ENG: J. MEYER 9/19/00
APP: J. MEYER 9/19/00



WEPX-342
SHT. 10



PLAN
SCALE: 1"=30'

NOTE: DRAIN DITCH INTO CONCRETE DRAIN BOXES

B 7/476 MSM	REV. PIPE SIZE FROM 8" TO 6"	
A 7/474 MSM	ADD DRAINAGE PORTION FOR UNIT-2 AND 3	
7/716 MSM	FOR BUD.	
REV. DATE	BY	SUBJECT
PLANT PARKING, ROADWAY AND TRANSFORMER AREA DRAINAGE PLAN WELSH POWER PLANT SOUTHWESTERN ELECTRIC POWER CO. POWER-CONSTRUCTION DEPARTMENT DIVISION		
APPROVED	DATE	IN CHARGE
APPROVED	DATE	BY
APPROVED	DATE	CHIEF ENGR.
DRAWN BY	DATE	WORK ORDER
DATE	NO.	SCALE
2-9-76	WE PX-68	1/2" = 30'
SHEET 2		



- NOTES:
1. BM1 IS A 1" BRASS DISK SET IN TOP OF CONCRETE INLET BOX FOR THE SECONDARY POND. ELEVATION = 340.01'
 2. BM2 IS A 1" BRASS SET IN CONCRETE SPILLWAY ALONG THE CANAL. ELEVATION = 336.20'
 3. TB=TOP OF BANK
EW=EDGE OF WATER
BM=BENCH MARK
 4. CONTOURS ARE 2.0' APART.
 5. LAKE ELEVATION PER WELSH POWER PLANT ON NOVEMBER 18, 2010 WAS 317.57 FEET MSL.

SURVEYOR CERTIFICATE:
 I HEREBY CERTIFY THAT THIS TOPOGRAPHICAL SURVEY WAS MADE ON THE GROUND UNDER MY SUPERVISION ON NOVEMBER 18, 2010, THAT THIS PLAT (MAP OR DRAWING) REPRESENTS THE FACTS FOUND AT THE TIME.

Mike Gardner
 MIKE GARDNER
 REGISTERED PROFESSIONAL LAND SURVEYOR
 NO. 5760, STATE OF TEXAS
 FIRM CERTIFICATE NO. 101011-00
 DATE: NOVEMBER 23, 2010
 REVISED: DECEMBER 6, 2010



TOPOGRAPHIC SURVEY

DIKE'S AT WELSH POWER PLANT
 FOR: GREG CARTER


Date	Revision/Description
12/6/10	ADDED LAKE LEVEL NOTE
12/6/10	ADDED CROSS SECTION SHEETS




5930 SUMMERHILL RD. | P.O. BOX 3788
 TEXARKANA, TEXAS 75501
 P 903.838.8533 | F 903.832.4700
 www.mtgenr.com

Drawn By MG	Checked By DW	Project No. 104021	Dwg. Date 11/19/10	File No.	Sheet No. 1
----------------	------------------	-----------------------	-----------------------	----------	----------------

15:308 (11/19/10) 15:308 at Welch Power Plant (11/19/10) 15:308 (11/19/10) 15:308 (11/19/10)



Sec 'AA' & BB
As Noted
Scale 1"=20'



SECTION 'C-C'
No Scale



SECTION 'D-D'
No Scale




NOTE
SEE GENERAL NOTES SHEET 1-1
SEE GENERAL NOTES SHEET 1-2

NO.	DATE	DESCRIPTION
1	10-1-58	PREPARED BY J. H. SMITH
2	10-1-58	CHECKED BY J. H. SMITH
3	10-1-58	APPROVED BY J. H. SMITH
4	10-1-58	REVISION
5	10-1-58	REVISION
6	10-1-58	REVISION
7	10-1-58	REVISION
8	10-1-58	REVISION
9	10-1-58	REVISION
10	10-1-58	REVISION

NO.	DATE	DESCRIPTION
1	10-1-58	PREPARED BY J. H. SMITH
2	10-1-58	CHECKED BY J. H. SMITH
3	10-1-58	APPROVED BY J. H. SMITH
4	10-1-58	REVISION
5	10-1-58	REVISION
6	10-1-58	REVISION
7	10-1-58	REVISION
8	10-1-58	REVISION
9	10-1-58	REVISION
10	10-1-58	REVISION

**ASH POND & SECONDARY
SETTLING AREA
WELSH POWER PLANT
SOUTHWESTERN ELECTRIC POWER CO.
CASON, TEXAS**

SARGENT & LUNDY
INCORPORATED
DRAUGHTSMEN
DRAWING NO.
S-12



REV	DATE	BY	SUBJECT
B	7/17/75	MJM	ADDED SIDEWALK, RECOVER HOLD
A	10/19/74	MJM	WIDER CHANNEL TO 15' BOD PILING
	9/1/74		REV FOR CORRECT
REV	DATE	BY	SUBJECT



ASH SETTLING BASIN DISCHARGE CONTROL STRUCT. WELSH POWER PLANT

SOUTHWESTERN ELECTRIC POWER CO.
G.O. CONSTRUCTION DEPARTMENT


APPROVED: _____ ENGR. IN CHARGE
APPROVED: _____ DIV. SUPV.
APPROVED: _____ CHIEF ENGR.

DRWN. BY: MJM
DATE: 7-11-74
SCALE: 3/8" = 1'-0"

TRAC. BY: _____
WORK ORDER NO. WEPX-31



LEGEND	
— e —	OVERHEAD ELECTRIC LINE
- - - - -	TOP OF BANK / SLOPE
- - - - -	TOE OF SLOPE / BANK
- - - - -	PIPING
- - - - -	EDGE OF DRIVE
- - - - -	EDGE OF GRAVEL
- - - - -	1.0' CONTOUR INTERVAL
- - - - -	5.0' CONTOUR INTERVAL
⊕	POWER POLE
⊞	PIPE LOCATION
	GUY WIRE
△	CONTROL MONUMENT
⊙	LIGHT POLE
[Hatched Box]	CONCRETE SURFACE
[Dotted Box]	AREA NOT SURVEYED



THE BEARINGS ARE BASED ON GRID NORTH WITHIN THE "TEXAS COORDINATE SYSTEM OF 1983, NORTH CENTRAL ZONE", NAD83 (CORR94, EPOCH 2002.0), WITH A BEARING OF NORTH 87 DEGREES 57 MINUTES 30 SECONDS EAST. THE COMBINED SCALE FACTOR TO GO FROM GRID TO SURFACE IS 1.00012. THE FOLLOWING CONTROL MONUMENTS WERE USED TO ESTABLISH THE BASIS OF BEARINGS:



CONTROL MONUMENT NO. 30001 N-7085417.3418 E-3087023.3084	CONTROL MONUMENT NO. 30010 N-7085452.9367 E-3086022.5268
--	--



SURVEYOR CERTIFICATE:
I HEREBY CERTIFY THAT THIS TOPOGRAPHICAL SURVEY WAS MADE ON THE GROUND UNDER MY SUPERVISION ON DECEMBER 14, 2009, THAT THIS PLAN (MAP OR DRAWING) REPRESENTS THE FACTS FOUND AT THE TIME.

Mike Gardner
MIKE GARDNER
REGISTERED PROFESSIONAL LAND SURVEYOR
NO. 5760, STATE OF TEXAS
FIRM CERTIFICATE NO. 101011-00
DATE: DECEMBER 17, 2009

TOPOGRAPHIC SURVEY		MTG <i>engineers & surveyors</i>
ASH STORAGE AREA WELSH POWER PLANT FOR: AEP		
Date	Revision/Description	5930 SUMMERHILL RD. P.O. BOX 3786 TEXARKANA TEXAS 75501 P 903.838.8533 F 903.832.4700 www.mtgenineers.com
Drawn By J.B.D.	Checked By M.G.	
Project No. 094027	Dwg. Date 12-17-09	©MTG 2009 TBPE NO. 354














NOTES:

1. When the level of the ash fines reaches the point where the fines start flowing across the spillway, then bags of sackrete can be installed to raise the spillway elevation.
2. When the level of the ash builds up to approx. elev. 355 along the north and east sides, a french drain system could be installed and drained to this outlet to help hold the water table down. Of course the water level in the storage area would have to be at elev. 351 or above for the french drain to function.
3. This Ash Storage Area has been designed to hold the water level as low as possible so the ash can be piled vertically with dozers, etc. The ash level needs to be approx. 4 ft. to 5 ft. above the water level in order to support heavy equipment.


REV.	W.O.	BY	DATE	SUBJECT	APPROVED	REV.	W.O.	BY	DATE	SUBJECT	APPROVED
C		BP	10-29-90	AS BUILT							
		BP	3-10-90	RELEASED FOR BIDS							

NEW BOTTOM ASH STORAGE AREA WELSH POWER PLANT		DEPT.
		DIV.
APPROVED		DATE: 3-10-00
DRWN. BY: BP	SCALE: 1"=100'	
SOUTHWESTERN ELECTRIC POWER CO.		SH. 1 of 2 DRWG. NO. WEPX-335


* - NOTE- THESE DIMENSIONS ARE SUBJECT TO ADJUSTMENT DEPENDING ON THE SAND / CLAY BALANCE VS. HAUL DISTANCE ON PROJECT.



DETAIL 6
50' ON CENTERS
(20 REQUIRED)



DETAIL 2
LOCATIONS & QUANTITIES DETERMINED IN FIELD.



DETAIL 3
LOCATIONS & QUANTITIES DETERMINED IN FIELD

REV	W.O.	BY	DATE	SUBJECT	APPROVED
B		BP	11/20/00	AS BUILT	
A		BP	5/18/00	RELEASED FOR CONSTRUCTION	
I		BP	1/19/00	RELEASED FOR BIDS SPEC. # 3449 (ADDENDUM #1)	
		BP	3/19/00	RELEASED FOR BIDS	

NEW BOTTOM ASH STORAGE AREA		DEPT.
WELSH POWER PLANT		DIV.
APPROVED		
DRWN. BY: BP	DATE: 3-10-00	
SCALE: AS SHOWN	W.O.	
SOUTHWESTERN ELECTRIC POWER CO.		SH. L#2
		DRWG. NO. WEPX-335

SURFACE TO DATUM VOLUME REPORT

Murray, Thomas & Griffin, Inc.
P.O. Box 3786
Texarkana, TX 75501
903-838-8533

Project: X:\2009 Projects\094025 ASH POND TOPO WELSH - GREG CARTER\
VOLUME CALC 4-12-10.pro

Report Generated: Monday, April 12, 2010 9:22:04 AM

Where the DTM surface is above the datum the volume is reported as fill.
Where the DTM surface is below the datum the volume is reported as excavation.

Shrinkage/swell factors: Excavation 1.0000 Fill 1.0000

DTM Surface Layer Name Datum Elevation

POINTS COMPOSITE 632 355.92


Volume limited to that within the constraining boundary - Object 18228
Area within boundary: 600,437.78 SQ FT (13.784 ACRES)
Total triangulated area: 594,973.58 SQ FT (13.659 ACRES)

Elev Range (ft)	Cut Volume (yd3)	Fill Volume (yd3)
346.13 > 346.92	213.3	0.0
346.92 > 347.92	1,674.4	0.0
347.92 > 348.92	2,922.6	0.0
348.92 > 349.92	3,724.2	0.0
349.92 > 350.92	4,444.3	0.0
350.92 > 351.92	5,674.4	0.0
351.92 > 352.92	7,552.1	0.0
352.92 > 353.92	10,632.0	0.0
353.92 > 354.92	14,916.3	0.0
354.92 > 355.92	19,411.2	0.0
355.92 > 355.94	0.0	0.0

Excavation Volume Beneath Datum (yd3) 71,164.9

Fill Volume Above Datum (yd3) 0.0

Net Difference: 71,164.9 yd3 excess volume beneath datum



HATCHED AREA IS THE PORTION BELOW ELEVATION 355.92



357.92

LOW ELEVATION ON EMERGENCY SPILLWAY

ASH POND VOLUME BELOW ELEVATION 355.92